
CITY OF POOLER

TO: ALL CONTRACTORS

FROM: CITY OF POOLER PUBLIC WORKS

SUBJECT: QUACCO ROAD / EASTHAVEN BLVD / SPANTO CREST SIGNAL
– ADDENDUM NO. 1

DATE: 2/8/2022

PLEASE SEE THE FOLLOWING ADDITIONS, CLARIFICATIONS AND/OR CHANGES:

Q1. Is timing included in the bid package?

A1. No, the City of Pooler will be responsible for timing after construction is completed.

Q2. If specific equipment is required, please provide?

A2. Temple sourced 332 cabinet / Controller 2070E with GDOT Max time software / PDC SSS88 load switch / PDC SSF88 flasher / LMD 622 Detectors / EDI 242L DC Isolator / Polara PBF9x15-PXX Push button with BDSP-010-x Push button Station / Battery backup is required

Q3. Should the mast arm foundations be bid under the GDOT new spec or the old spec?

A3. New