

Site Work Plans

FOR

Mosaic Galleria

125 High Avenue


Pooler, Georgia 31322

FOR


Mosaic Five, LLC

P.O. Box 6465

Beaufort, South Carolina 29906



September, 2025



BOSWELL DESIGN SERVICES, INC.
OFFICE : 4700 EAST HIGHWAY 80
Unit N, Suite 1
MAILING : 103 NASSAU DRIVE
SAVANNAH, GEORGIA 31410
912 - 897 - 6932
LAHBOS@Bellsouth.net

DEPARTMENT OF
PLANNING & DEVELOPMENT
APPROVED BY: *tiarles*
DATE: 10:07 am, Nov 25 2025


DWG. NO.	DESCRIPTION
C1	COVER SHEET, SCHEDULE OF DRAWINGS AND VICINITY MAP
C2	EXISTING SITE PLAN
C3	DEMOLITION PLAN
C4	STAKING AND SIGNING PLAN
C5	PAVING, GRADING AND DRAINAGE PLAN
C6	UTILITY PLAN, NOTES AND DETAILS
C7	PROFILES AND DETAILS
C8	LANDSCAPE PLAN, NOTES AND DETAILS
C9	IRRIGATION PLAN
C10	DETAILS
C11	DETAILS
C12	DETAILS
C13	PAD DETAILS
C14	LIGHTING PLAN AND DETAILS
C15	SOIL EROSION AND SEDIMENT CONTROL PLAN - PHASE I
C16	SOIL EROSION AND SEDIMENT CONTROL PLAN - PHASE II
C17	SOIL EROSION AND SEDIMENT CONTROL PLAN - PHASE III
C18	TRAP DETAILS
C19	NOTES AND DETAILS
C20	NOTES AND DETAILS
C21	NOTES AND DETAILS
C22	NOTES AND DETAILS
C23	NOTES AND DETAILS
C24	NOTES AND DETAILS
C25	NOTES AND DETAILS
C26	NOTES AND DETAILS
C27	TURN RADIUS EXHIBIT
C28	GSWCC CHECKLIST

SCHEDULE OF DRAWINGS

SPECIAL ORDINANCE NOTE :
1. IN CASE OF CONFLICT BETWEEN THESE PLANS AND THE CITY OF POOLER'S ORDINANCES, STANDARDS, SPECIFICATIONS OR DETAILS, THE CITY OF POOLER, STANDARDS ARE TO TAKE PRECEDENCE.

LANDSCAPE AND UTILITY BOND NOTES :
1. ALL LANDSCAPE AND UTILITY BONDS THAT ARE REQUIRED BY THE CITY OF POOLER ARE TO BE SUPPLIED AND MAINTAINED BY THE SITE OWNER.





STREAM BUFFER ENCROACHMENT NOTES :

1. NEW STRUCTURES ON THIS PROJECT DO NOT ENCR OACH IN THE 25 OR 50 FOOT STREAM BUFFER.
2. NON-EXMPT ACTIVITIES SHALL NOT BE CONDUCTED WITHIN THE 25 OR 50 FOOT UNDISTURBED STREAM BUFFERS AS MEASURED FROM THE POINT OF WRESTED VEGETATION OR WITHIN 25 FEET OF THE COASTAL MARSHLAND BUFFER AS MEASURED FROM THE JURISDICTIONAL DETERMINATION LINE WITHOUT FIRST ACQUIRING THE NECESSARY VARIANCES AND PERMITS.

1. IN CASE OF CONFLICT BETWEEN THESE PLANS AND THE CITY OF POOLER'S ORDINANCES STANDARDS, SPECIFICATIONS OR DETAILS, THE CITY OF POOLER, STANDARDS ARE TO TAKE PRECEDENCE.

1. CONTRACTOR IS TO VERIFY ALL DEEDS, EASEMENTS, ETC. WITH THE TOLLER PLANNING AND ZONING DEPARTMENT PRIOR TO CONSTRUCTION ACTIVITIES.

- SPECIAL F.F. NOTES :
1. CONTRACTOR TO VERIFY FEMA ELEVATIONS PRIOR TO ANY CONSTRUCTION ACTIVITIES AND COORDINATE WITH GOVERNING AGENCY REQUIREMENTS.
 2. CONTRACTOR TO COORDINATE FINISH FLOOR ELEVATIONS WITH STRUCTURAL, ARCHITECTURAL AND M.E.P. PLANS.

- NOTES:
1. CONTRACTOR IS TO COORDINATE ALL GAS, LIGHTING, ELECTRICAL, PHONE, CABLE AND ANY OTHER REQUIRED UTILITIES WITH THE APPROPRIATE UTILITY AGENCIES.
 2. CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL EXISTING UTILITIES PRIOR TO COMMENCING OF CONSTRUCTION ACTIVITIES AND FOR AVOIDING CONFLICT WITH SAME. ANY DAMAGE TO EXISTING UTILITIES SHALL BE REPAIRED AT THE EXPENSE OF THE CONTRACTOR.
 3. CONTRACTOR IS TO COORDINATE ALL DEMOLITION WORK WITH THE OWNER. ALL ITEMS NOT TO BE RELOCATED OR GIVEN TO THE OWNER WILL BECOME THE PROPERTY OF THE CONTRACTOR.
 4. REMOVE ALL TREES AS NECESSARY FOR PROPOSED CONSTRUCTION.

PROJECT ADDRESS : 125 High Avenue
Pooler, Georgia 31322

CURRENT ZONING : PUD PHASE 7 SAVANNAH QUARTERS

SITE SIZE : 1.91 ACRES

ESTIMATED DISTURBED AREA : 2.5 ACRES

TOTAL PERVIOUS AREA: 0.7 ACRES
TOTAL IMPERVIOUS AREA: 1.2 ACRES (63% IMPERVIOUS)

SETBACKS :
FRONT = 30'
REAR = 15'
SIDE = 20'

MAX. BUILDING HEIGHT = 125'-0"
PROPOSED BUILDING HEIGHT = 21'-3"

OWNER : Mosaic Fire, LLC
(contract: D.J. Desai)
P.O. Box 6465
Beaufort, South Carolina 29906

PRIMARY PERMITTEE EMAIL : djdesai@hdccompanyinc.com

PHONE : 843-379-9405

3.31.0.1 REQUIRED ACCESS.


APPROVED VEHICLE ACCESS FOR FIREFIGHTING SHALL BE PROVIDED TO ALL CONSTRUCTION OR MAINTENANCE VEHICLES. ACCESS SHALL BE PROVIDED TO WITHIN 150 FEET OF THE NEAREST PERMANENT FIRE DEPARTMENT CONNECTIONS. VEHICLE ACCESS SHALL BE PROVIDED BY EITHER TEMPORARY OR PERMANENT ROADS CAPABLE OF SUPPORTING VEHICLE LOADING UNDER ALL WEATHER CONDITIONS. VEHICLE ACCESS SHALL BE MAINTAINED UNTIL PERMANENT FIRE APPARATUS ROADS ARE AVAILABLE.


2. FIRE LANE SIGNS SHALL BE SPACED AT A MINIMUM OF 200 FEET APART. SIZE TO BE 12" X 18" WITH A WHITE REFLECTING BACKGROUND AND RED LETTERS AND SHALL READ AS FOLLOWS: "FIRE LANE - NO PARKING - TOW-AWAY ZONE".

3. AS PER FIRE CODE, FIRE FIGHTING APPARATUS MUST BE ABLE TO ACCESS TO WITHIN 150' OF ANY PART OF BUILDING.

1. RETAIL = B OCCUPANCY (SECTION 304.1)
2. SPRINKLER PROTECTION IS NOT REQUIRED AS PER CHAPTER 9
3. FIRE PROTECTION IS PROVIDED

1. THIS DEVELOPMENT IS WITHIN FLOOD ZONE AREA "X" ACCORDING TO F.I.R.M. COMMUNITY PANEL NUMBER 130561C0108 & 130561C0109, MAP REVISED AUGUST 16, 2018 (NAVD 88).
2. THIS SITE IS IN ZONE "X" AND IS NOT LOCATED WITHIN THE 100 YEAR FLOOD ZONE.
3. CONTRACTOR IS TO VERIFY FEMA ELEVATIONS PRIOR TO ANY CONSTRUCTION ACTIVITIES.





OUTPARCEL 15
PIN: 51009 01007
SHAN POOLER LAND INVESTMENT
ZONING: PUD

1. IN CASE OF CONFLICT BETWEEN THESE PLANS AND THE CITY OF POOLER'S ORDINANCES STANDARDS, SPECIFICATIONS OR DETAILS, THE CITY OF POOLER, STANDARDS ARE TO TAKE PRECEDENCE.

1. THIS DEVELOPMENT IS WITHIN FLOOD ZONE AREA "X" ACCORDING TO F.I.R.M. COMMUNITY PANEL NUMBER 130561C0108 & 130561C0109, MAP REVISED AUGUST 16, 2018 (NAVD 88).
2. THIS SITE IS IN ZONE "X" AND IS NOT LOCATED WITHIN THE 100 YEAR FLOOD ZONE.
3. CONTRACTOR IS TO VERIFY FEMA ELEVATIONS PRIOR TO ANY CONSTRUCTION ACTIVITIES.

1. ALL ROAD CLOSURES, DETOURS AND ETC. ARE TO BE COORDINATED WITH THE CITY OF POOLER, GEORGIA.
2. ANY AND ALL NECESSARY PERMITS MUST BE OBTAINED FROM THE CITY OF POOLER PRIOR TO COMMENCEMENT OF ANY WORK.
3. CONTRACTOR IS TO OBTAIN A R.O.W. PERMIT PRIOR TO PERFORMING ANY WORK WITHIN CITY OF POOLER RIGHT-OF-WAY.
4. CHLORINATED DISINFECTED WATER SHALL NOT BE DISCHARGED INTO THE STORMWATER SYSTEM.


1. NEW STRUCTURES ON THIS PROJECT DO NOT ENCROUGH IN THE 25 OR 50 FOOT STREAM BUFFER.
2. NON-EXEMPT ACTIVITIES SHALL NOT BE CONDUCTED WITHIN THE 25 OR 50 FOOT UNDISTURBED STREAM BUFFERS AS MEASURED FROM THE POINT OF WRESTED VEGETATION OR WITHIN 25 FEET OF THE COASTAL MARSHLAND BUFFER AS MEASURED FROM THE JURISDICTIONAL DETERMINATION LINE WITHOUT FIRST ACQUIRING THE NECESSARY VARIANCES AND PERMITS.

1. Survey information : Gardner Surveying
2. Date of Original Survey : May, 2024
3. Datum : NAVD 88

1. CONTRACTOR TO COORDINATE ALL GAS, LIGHTING, ELECTRICAL, PHONE, CABLE AND ANY OTHER REQUIRED UTILITIES WITH THE APPROPRIATE UTILITY AGENCIES,
2. CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL EXISTING UTILITIES PRIOR TO COMMENCING OF CONSTRUCTION ACTIVITIES AND FOR AVOIDING CONFLICT WITH SAME. ANY DAMAGE TO EXISTING UTILITIES SHALL BE REPAIRED AT THE EXPENSE OF THE CONTRACTOR.
3. CONTRACTOR IS TO COORDINATE ALL DEMOLITION WORK WITH THE OWNER. ALL ITEMS NOT TO BE RELOCATED OR GIVEN TO THE OWNER WILL BECOME THE PROPERTY OF THE CONTRACTOR.
4. REMOVE ALL TREES AS NECESSARY FOR PROPOSED CONSTRUCTION.

IF THE CONTRACTOR KNOWS OR CAN REASONABLY BE EXPECTED TO HAVE KNOWN OF AN ERROR, DISCREPANCY OR CONFLICT IN THE PLANS, SPECIFICATIONS OR CONSTRUCTION STAKING AND FAILS TO REPORT THE PROBLEM PRIOR TO CONSTRUCTION, HE SHALL NOT BE ENTITLED TO COMPENSATION FOR ANY WORK OR EXPENSE INCURRED BY HIM FOR WORK REQUIRED TO BE RE-CONSTRUCTED BECAUSE OF SAID ERROR, DISCREPANCY OR CONFLICT.

$$I^* = 2C$$



SPECIAL SIGNAGE AND STRIPING NOTES :

1. STOP SIGNS SHALL BE HIGH INTENSITY OR DIAMOND GRADE.
2. PAVEMENT MARKINGS ARE TO BE THERMOPLASTIC.
3. ALL SIGNS ARE TO BE IN ACCORDANCE WITH MUTCD.

1. DIMENSIONS ARE IN FEET AND DECIMAL OF FEET UNLESS NOTED OTHERWISE.

2. LIMITS OF CLEARING AND GRUBBING SHALL MATCH THE PROPERTY LINE BOUNDARY OR AS SHOWN ON THE PLANS. COORDINATE ALL CLEARING ACTIVITIES WITH THE ENGINEER/OWNER.

3. ALL COORDINATES AND BEARINGS SHOWN ARE BASED ON A SITE COORDINATE SYSTEM. CONTRACTOR SHALL VERIFY PRIOR TO THE START OF CONSTRUCTION.

4. BENCHMARKS SHALL BE VERIFIED BY THE CONTRACTOR AS TO LOCATION AND ELEVATION PRIOR TO THE START OF CONSTRUCTION.

5. ALL ANGLES ARE 90 DEGREES UNLESS OTHERWISE NOTED.

6. CONTRACTOR SHALL VERIFY THAT OVERALL SITE DIMENSIONS AGREE WITH THE INCREMENTAL LAYOUT DIMENSIONS AS SHOWN. ANY DISCREPANCIES WITH DIMENSIONS AND COORDINATES OR PROPERTY LINES SHALL BE ADJUSTED AND APPROVED BY THE ENGINEER.

7. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DEVELOPING HORIZONTAL AND VERTICAL CONTROL ON THE SITE BASED ON EXISTING MONUMENTS. ALL COSTS INVOLVED IN LOCATING THE EXISTING MONUMENTS AND CARRYING THE STAKING LAYOUT TO THE SITE SHALL BE BORNE BY THE CONTRACTOR.

8. CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL EXISTING UTILITIES PRIOR TO COMMENCING OF CONSTRUCTION AND FOR AVOIDING CONFLICT WITH SAME. ANY DAMAGE TO EXISTING UTILITIES SHALL BE REPAIRED AT THE EXPENSE OF THE CONTRACTOR.

9. CONTRACTOR TO VERIFY ACTUAL BUILDING DIMENSIONS WITH ARCH. PLANS.

10. ALL RADII ARE 5' UNLESS OTHERWISE NOTED.

SPECIAL AE AND VE ZONE NOTES :

1. BUILDINGS IN "AE" ZONES ARE TO HAVE THE FINISHED FLOOR SET A MINIMUM OF 1' ABOVE FLOOD. VERIFY WITH MUNICIPALITY.
2. BUILDINGS IN "VE" ZONES ARE TO HAVE THE LOWEST HORIZONTAL STRUCTURAL MEMBER SET A MINIMUM OF 1' ABOVE FLOOD. VERIFY WITH MUNICIPALITY.
3. BUILDINGS IN AE AND VE ZONES ARE TO HAVE ALL ELECTRICAL, PLUMBING, HVAC, DUCTWORK AND OTHER EQUIPMENT TO BE A MINIMUM OF 1' ABOVE FLOOD. VERIFY WITH MUNICIPALITY.
4. FLOOD VENTS ARE REQUIRED IN "AE" ZONES AND ARE TO HAVE 1 SQUARE INCH / SQUARE FOOT OF ENCLOSED AREA WITH A MINIMUM ROUND OPENING OF 3". A MINIMUM OF 2 OPENINGS WITH ALL OPENINGS EVENLY SPACED AROUND PERIMETER. BOTTOM OF OPENING SHALL BE 1/2" OR LESS ABOVE ADJACENT GRADE.
5. BREAK AWAY WALLS ARE REQUIRED IN "VE" ZONES.
6. ENCLOSED CRAWL SPACES ARE TO HAVE 1 5F SCREENED VENT PER 150 SF OF CRAWL SPACE AREA WITH A VENT LOCATED A MAX. OF 3' FROM EACH CORNER.
7. COORDINATE SITE WORK AND FINISHED FLOOR ELEVATIONS WITH ARCHITECTURAL PLANS TO MAKE SURE BUILDING ELEVATIONS ARE SET AS PER CODE. VERIFY WITH MUNICIPALITY.
8. STRUCTURES IN FLOOD ZONES IN CHATHAM COUNTY ARE TO HAVE THE LOWEST OCCUPABLE AREA (INCLUDING PORCHES) FINISHED FLOOR SET 3' ABOVE THE FLOOD ZONE ELEVATION (BFE + 3). VERIFY WITH MUNICIPALITY.
9. IN CHATHAM COUNTY, BUILDINGS IN AE AND VE ZONES ARE TO HAVE ALL ELECTRICAL (INTERIOR, EXTERIOR) INCLUDING DISCONNECT BOXES, PLUMBING, HVAC, OUTLETS, SWITCHES, DUCTWORK AND OTHER EQUIPMENT A MINIMUM OF 3' ABOVE FLOOD. VERIFY WITH MUNICIPALITY.

STREAM BUFFER ENCROACHMENT NOTES :

1. NEW STRUCTURES ON THIS PROJECT DO NOT ENCRUGH IN THE 25 OR 50 FOOT STREAM BUFFER.
2. NON-EXEMPT ACTIVITIES SHALL NOT BE CONDUCTED WITHIN THE 25 OR 50 FOOT UNDISTURBED STREAM BUFFERS AS MEASURED FROM THE POINT OF WRESTED VEGETATION OR WITHIN 25 FEET OF THE COASTAL MARSHLAND BUFFER AS MEASURED FROM THE JURISDICTIONAL DETERMINATION LINE WITHOUT FIRST ACQUIRING THE NECESSARY VARIANCES AND PERMITS.

PARKING CALCULATIONS:

NEW RETAIL BUILDINGS = 12,000 SF
NEW RESTAURANTS = 72 SEATS TOTAL

REQUIRED RETAIL PARKING = $\left(\frac{1 \text{ SPACE}}{250 \text{ SF}} \right) \left(12,000 \right) = 48 \text{ SPACES REQUIRED}$

REQUIRED RESTAURANT PARKING = $\left(\frac{1 \text{ SPACE}}{4 \text{ SEATS}} \right) \left(72 \text{ SEATS} \right) = 18 \text{ SPACES REQUIRED}$

TOTAL SPACES REQUIRED = 48 + 18 = 66 SPACES REQUIRED

TOTAL SPACES SUPPLIED = 66 SPACES

HANDICAP SPACES SUPPLIED = 3 SPACES

VAN ACCESSIBLE SPACES SUPPLIED = 1 SPACE
(1 VAN SPACE / 6 H.C. SPACES AS PER ADA 208.2.4)

PARKING SPACES BASED ON CITY OF POOLER PARKING ORDINANCE ASSUMING A RETAIL AND RESTAURANT OCCUPANCY

FIRE PROTECTION WATER :

AS PER 2018 IBC:

1. RETAIL = B OCCUPANCY (SECTION 304.1)
2. SPRINKLER PROTECTION IS NOT REQUIRED AS PER CHAPTER 9
3. FIRE PROTECTION IS PROVIDED

SITE FIRE PROTECTION NOTES :

1. ACCESS FOR FIREFIGHTING
3310.10 REQUIRED ACCESS.
APPROVED VEHICLE ACCESS FOR FIREFIGHTING SHALL BE PROVIDED TO ALL CONSTRUCTION OR DEMOLITION SITES. VEHICLE ACCESS SHALL BE PROVIDED TO WITHIN 100 FEET OF TEMPORARY OR PERMANENT FIRE DEPARTMENT CONNECTIONS. VEHICLE ACCESS SHALL BE PROVIDED BY EITHER TEMPORARY OR PERMANENT ROADS CAPABLE OF SUPPORTING VEHICLE LOADING UNDER ALL WEATHER CONDITIONS. VEHICLE ACCESS SHALL BE MAINTAINED UNTIL PERMANENT FIRE APPARATUS ROADS ARE AVAILABLE.
2. FIRE LANE SIGNS SHALL BE SPACED AT A MINIMUM OF 200 FEET APART, SIZE TO BE 12" x 18" WITH A WHITE REFLECTING BACKGROUND AND RED LETTERS AND SHALL READ AS FOLLOWS: "FIRE LANE - NO PARKING - TOW-AWAY ZONE".
3. AS PER FIRE CODE, FIRE FIGHTING APPARATUS MUST BE ABLE TO ACCESS TO WITHIN 150' OF ANY PART OF BUILDING.

PAVEMENT MARKING NOTES :

1. ALL SIGNAGE AND STRIPING SHALL BE IN ACCORDANCE WITH THE "MANUAL ON UNIFORM TRAFFIC CONTROL DESIGN (MUTCD)".

POOLER ORDINANCE NOTES :

1. CONTRACTOR IS TO VERIFY ALL BSL'S, BUFFERS, ETC. WITH THE POOLER PLANNING AND ZONING DEPARTMENT PRIOR TO CONSTRUCTION ACTIVITIES.

SPECIAL HANDICAP RAMP NOTES :

1. ALL HANDICAP RAMP SHALL BE CONSTRUCTED AND "TINTED" AS PER ADA GUIDELINES AND REQUIREMENTS.

CURB RADII NOTE :

ALL CURB RADII ARE 5' U.N.O.

GREENSPACE CALCULATIONS :

TOTAL SITE = 1.90 AC.
PAVING / BUILDING / ETC. = 1.20 AC.
GREENSPACE = 0.70 AC.

0.70 AC / 1.90 AC = 0.3684 = 37 % GREENSPACE

SIWALK NOTES :

1. ALL SIWALKS ARE TO BE ADA COMPLIANT.
2. PEDESTRIAN PATHS IN PARKING AREAS ARE TO BE 6' WIDE - PATTERN, COLOR AND TEXTURE TO BE COORDINATED WITH OWNER AND THE CITY OF POOLER.

SPECIAL CONSTRUCTION NOTE:

IF THE CONTRACTOR KNOWS OR CAN REASONABLY BE EXPECTED TO HAVE KNOWN OF AN ERROR, DISCREPANCY OR CONFLICT IN THE PLANS, SPECIFICATIONS OR CONSTRUCTION STAKING AND FAILS TO REPORT THE PROBLEM PRIOR TO CONSTRUCTION, HE SHALL NOT BE ENTITLED TO COMPENSATION FOR ANY WORK OR EXPENSE INCURRED BY HIM FOR WORK REQUIRED TO BE RE-CONSTRUCTED BECAUSE OF SAID ERROR, DISCREPANCY OR CONFLICT.

SITE LIGHTING NOTE :

ALL SITE LIGHTING IS TO BE AS PER OWNER AND IS TO BE COORDINATED WITH OWNER FOR POLE PLACEMENT, APPROVAL BY POOLER, ETC.

TRAFFIC / RIGHT-OF-WAY AND DISCHARGE NOTES:


1. ALL ROAD CLOSINGS, DETOURS AND ETC. ARE TO BE COORDINATED WITH THE CITY OF POOLER, GEORGIA.
2. ANY AND ALL NECESSARY PERMITS MUST BE OBTAINED FROM THE CITY OF POOLER PRIOR TO COMMENCEMENT OF ANY WORK.
3. CONTRACTOR IS TO OBTAIN A R.O.W. PERMIT PRIOR TO PERFORMING ANY WORK WITHIN CITY OF POOLER RIGHT-OF-WAY.
4. CHLORINATED DISINFECTED WATER SHALL NOT BE DISCHARGED INTO THE STORMWATER SYSTEM.

PAVING SURFACE LEGEND

HEAVY DUTY	
STANDARD DUTY	
CRUSHER RUN	
CONCRETE	
STABILIZED EARTH	
GOOT PAVING	
FUTURE BUILDING	
DUMPED STON RIP-RAP	

STAKING AND SIGNING PLAN

1" = 20'



REVISIONS

CHANGED

DRAWN

DESIGNED

MAS

MS

MS

DATE

JOB NO.

SCALE

OCT 6, 2025

as shown

BOSWELL DESIGN SERVICES, INC.

OFFICE: 4700 EAST HIGHWAY 80
Unit N, Suite 1
MAILING: 103 NASSAU DRIVE
SAVANNAH, GEORGIA 31410
912 - 897 - 6932
LAHBOS@bellsouth.net

MOSAIC GALLERIA
125 HIGH AVENUE
POOLER, GEORGIA 31322
MOSAIC FIVE, LLC
BEAUFORT, SOUTH CAROLINA

STAKING AND SIGNING PLAN


CONTACT A MINIMUM OF 72 HOURS PRIOR TO DIGGING

UTILITIES PROTECTION CENTER
1-800-282-7411

DRAWING NUMBER

C-4

4 OF 28 SHEETS



- NOTES:
1. CONTRACTOR IS TO COORDINATE ALL GAS, LIGHTING, ELECTRICAL, PHONE, CABLE AND ANY OTHER REQUIRED UTILITIES WITH THE APPROPRIATE UTILITY AGENCIES.
 2. CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL EXISTING UTILITIES PRIOR TO COMMENCING OF CONSTRUCTION ACTIVITIES AND FOR AVOIDING CONFLICT WITH SAME. ANY DAMAGE TO EXISTING UTILITIES SHALL BE REPAIRED AT THE EXPENSE OF THE CONTRACTOR.
 3. CONTRACTOR IS TO COORDINATE ALL DEMOLITION WORK WITH THE OWNER. ALL ITEMS NOT TO BE RELOCATED OR GIVEN TO THE OWNER WILL BECOME THE PROPERTY OF THE CONTRACTOR.
 4. REMOVE ALL TREES AS NECESSARY FOR PROPOSED CONSTRUCTION.

- GEOTECHNICAL NOTES:
1. A GEOTECHNICAL INVESTIGATION SHOULD BE PERFORMED PRIOR TO PAVING ROADS FOR PAVEMENT DESIGN RECOMMENDATIONS AND AS PER THE CITY OF POOLERS STANDARD DETAIL.
 2. IT IS STRONGLY RECOMMENDED THAT A GEOTECHNICAL INVESTIGATION IS PERFORMED BY A REGISTERED GEOTECHNICAL ENGINEER IN THE STATE OF GEORGIA PRIOR TO BUILDING SLABS BEING POURED FOR RECOMMENDATIONS FOR SOAK DRAINS, FOUNDATION DESIGN, ETC.

- FEMA MAP NOTES:
1. THIS DEVELOPMENT IS WITHIN FLOOD ZONE AREA "X" ACCORDING TO F.I.R.M. COMMUNITY PANEL NUMBER 130561C0108 & 130561C0109, MAP REVISED AUGUST 16, 2018 (NAVD 88).
 2. THIS SITE IS IN ZONE "X" AND IS NOT LOCATED WITHIN THE 100 YEAR FLOOD ZONE.
 3. CONTRACTOR IS TO VERIFY FEMA ELEVATIONS PRIOR TO ANY CONSTRUCTION ACTIVITIES.

- SPECIAL ORDINANCE NOTE:
1. IN CASE OF CONFLICT BETWEEN THESE PLANS AND THE CITY OF POOLERS ORDINANCES STANDARDS, SPECIFICATIONS OR DETAILS, THE CITY OF POOLER, STANDARDS ARE TO TAKE PRECEDENCE.


- SPECIAL DETENTION POND NOTE:
1. DETENTION FOR THIS PROJECT IS BEING ACHIEVED BY UTILIZING THE EXTG PARK DETENTION POND AND THEREFOR DETENTION IS NOT BEING PLANNED FOR THIS PROJECT

- STORM AND UTILITIES MANHOLE AND BOX NOTES:
1. INVERT ELEVATIONS ARE TO BE CONSIDERED AS PIPE INVERTS AND NOT AS THE INVERT OF THE MANHOLE, BOX, ETC.

- FIRE PROTECTION WATER:
- AS PER 2018 IBC:
1. RETAIL - B OCCUPANCY (SECTION 304.1)
 2. SPRINKLER PROTECTION IS NOT REQUIRED AS PER CHAPTER 9
 3. FIRE PROTECTION IS PROVIDED

- CULVERT PIPE INSTALLATION NOTES:
1. CULVERTS ARE TO BE INSTALLED AS PER CITY OF POOLER DETAILS AND SPECS
 2. CULVERT DETAILS AND SPECS WERE NOT AVAILABLE AT THE TIME OF THIS SUBMITTAL AND SHALL BE OBTAINED FROM CITY OF POOLER STORMWATER DEPARTMENT.

- SUBGRADE DRAIN NOTES:
1. SEE DETAILS
 2. SUBGRADE DRAINS SHALL BE ADDED TO STORM DRAIN INLETS DUE TO GROUND WATER TABLE.
 3. SUBGRADE DRAIN WILL CONSIST OF 6" DIA. PERFORATED PIPE EMBEDDED IN GRANULAR MATERIAL.
 4. DRAINS SHALL EXTEND 10 LF IN TWO DIRECTIONS FROM THE INLET.
 5. DRAINS MAY BE EXTENDED MORE THAN 10 LF IF INSTRUCTED BY OWNER OR HISHER REPRESENTATIVE AS CONDITIONS DICTATE.
 6. DRAINS SHALL BE INSTALLED AT A UNIFORM SLOPE TOWARDS THE INLET.



- SIDEWALK NOTES:
1. ALL SIDEWALKS ARE TO BE ADA COMPLIANT.
 2. PEDESTRIAN PATHS IN PARKING AREAS ARE TO BE 6' WIDE - PATTERN, COLOR AND TEXTURE TO BE COORDINATED WITH OWNER AND THE CITY OF POOLER.

- STREAM BUFFER ENCROACHMENT NOTES:
1. NEW STRUCTURES ON THIS PROJECT DO NOT ENCROACH IN THE 25 OR 50 FOOT STREAM BUFFER.
 2. NON-EXEMPT ACTIVITIES SHALL NOT BE CONDUCTED WITHIN THE 25 OR 50 FOOT UNDISTURBED STREAM BUFFERS AS MEASURED FROM THE POINT OF WRESTED VEGETATION OR WITHIN 25 FEET OF THE COASTAL MARSHLAND BUFFER AS MEASURED FROM THE JURISDICTIONAL DETERMINATION LINE WITHOUT FIRST ACQUIRING THE NECESSARY VARIANCES AND PERMITS.

- SPECIAL CONSTRUCTION NOTE:
- IF THE CONTRACTOR KNOWS OR CAN REASONABLY BE EXPECTED TO HAVE KNOWN OF AN ERROR, DISCREPANCY OR CONFLICT IN THE PLANS, SPECIFICATIONS OR CONSTRUCTION STRAING AND FAILS TO REPORT THE PROBLEM PRIOR TO CONSTRUCTION, HE SHALL NOT BE ENTITLED TO COMPENSATION FOR ANY WORK OR EXPENSE INCURRED BY HIM FOR WORK REQUIRED TO BE RE-CONSTRUCTED BECAUSE OF SAID ERROR, DISCREPANCY OR CONFLICT.

- SPECIAL AE AND VE ZONE NOTES:
1. BUILDINGS IN "AE" ZONES ARE TO HAVE THE FINISHED FLOOR SET A MINIMUM OF 1' ABOVE FLOOD. VERIFY WITH MUNICIPALITY.
 2. BUILDINGS IN "VE" ZONES ARE TO HAVE THE LOWEST HORIZONTAL STRUCTURAL MEMBER SET A MINIMUM OF 1' ABOVE FLOOD. VERIFY WITH MUNICIPALITY.
 3. BUILDINGS IN AE AND VE ZONES ARE TO HAVE ALL ELECTRICAL, PLUMBING, HVAC, DUCTWORK AND OTHER EQUIPMENT TO BE A MINIMUM OF 1' ABOVE FLOOD. VERIFY WITH MUNICIPALITY.
 4. FLOOD VENTS ARE REQUIRED IN "AE" ZONES AND ARE TO HAVE 1 SQUARE INCH / SQUARE FOOT OF ENCLOSED AREA WITH A MINIMUM ROUND OPENING OF 3", A MINIMUM OF 2 OPENINGS WITH ALL OPENINGS EVENLY SPACED AROUND PERIMETER. BOTTOM OF OPENING SHALL BE 1'2" OR LESS ABOVE ADJACENT GRADE.
 5. BREAK AWAY WALLS ARE REQUIRED IN "VE" ZONES.
 6. ENCLOSED CRAWL SPACES ARE TO HAVE 1 5/8" SCREENED VENT PER 150 SF OF CRAWL SPACE AREA WITH A VENT LOCATED A MAX. OF 3' FROM EACH CORNER.
 7. COORDINATE SITE WORK AND FINISHED FLOOR ELEVATIONS WITH ARCHITECTURAL PLANS TO MAKE SURE BUILDING ELEVATIONS ARE SET AS PER CODE. VERIFY WITH MUNICIPALITY.
 8. STRUCTURES IN FLOOD ZONES IN CHATHAM COUNTY ARE TO HAVE THE LOWEST OCCURABLE AREA (INCLUDING PORCHES) FINISHED FLOOR SET 3' ABOVE THE FLOOD ZONE ELEVATION (BFE + 3). VERIFY WITH MUNICIPALITY.
 9. IN CHATHAM COUNTY, BUILDINGS IN AE AND VE ZONES ARE TO HAVE ALL ELECTRICAL (INTERIOR, EXTERIOR) INCLUDING DISCONNECT BOXES, PLUMBING, HVAC, OUTLETS, SWITCHES, DUCTWORK AND OTHER EQUIPMENT A MINIMUM OF 3' ABOVE FLOOD. VERIFY WITH MUNICIPALITY.
- SPECIAL F.F. NOTES:
1. CONTRACTOR TO VERIFY FEMA ELEVATIONS PRIOR TO ANY CONSTRUCTION ACTIVITIES AND COORDINATE WITH GOVERNING AGENCY REQUIREMENTS.
 2. CONTRACTOR TO COORDINATE FINISH FLOOR ELEVATIONS WITH STRUCTURAL, ARCHITECTURAL AND M.E.P. PLANS.

- SITE FIRE PROTECTION NOTES:
1. ACCESS FOR FIREFIGHTING
3310.10 REQUIRED ACCESS
APPROVED VEHICLE ACCESS FOR FIREFIGHTING SHALL BE PROVIDED TO ALL CONSTRUCTION OR DEMOLITION SITES. VEHICLE ACCESS SHALL BE PROVIDED TO WITHIN 100 FEET OF TEMPORARY OR PERMANENT FIRE DEPARTMENT CONNECTIONS. VEHICLE ACCESS SHALL BE PROVIDED BY EITHER TEMPORARY OR PERMANENT ROADS CAPABLE OF SUPPORTING VEHICLE LOADING UNDER ALL WEATHER CONDITIONS. VEHICLE ACCESS SHALL BE MAINTAINED UNTIL PERMANENT FIRE APPARATUS ROADS ARE AVAILABLE.
 2. FIRE LANE SIGNS SHALL BE SPACED AT A MINIMUM OF 200 FEET APART, SIZE TO BE 12" x 18" WITH A WHITE REFLECTING BACKGROUND AND RED LETTERS AND SHALL READ AS FOLLOWS: "FIRE LANE - NO PARKING - TOW-AWAY ZONE".
 3. AS PER FIRE CODE, FIRE FIGHTING APPARATUS MUST BE ABLE TO ACCESS TO WITHIN 150' OF ANY PART OF BUILDING.

- SPECIAL CONSTRUCTION NOTES:
1. SITE AND BUILDING CONTRACTOR IS TO OBTAIN, REVIEW AND FOLLOW THE RECOMMENDATIONS SET FORTH BY THE GEOTECHNICAL REPORT.
 2. GROUNDWATER MUST BE LOWERED DURING CONSTRUCTION BY ANY MEANS APPROVED BY THE GEOTECHNICAL ENGINEER.
 3. DE-WATERING MAY BE ACCOMPLISHED BY WELLPOINTS AND / OR DITCHES WITH SLUPS AND PUMPS.
 4. STIFFING OF PROJECT SITE DEPTHS MAY BE FROM 2 TO IN EXCESS OF 5 FEET BELOW THE GROUND SURFACE.
 5. FILL AND / OR BACKFILL SHALL CONSIST OF COARSE-GRAINED SOILS CLASSIFIED AS SW, SP, SM OR SP-SM WITH A MINIMUM OF 15% PASSING A #200 SIEVE.
 6. BACKFILL FOR PAVING SHALL BE PLACED IN 6 INCH LIFTS AND COMPACTED TO 95% DENSITY IN ACCORDANCE WITH ASTM D-1557.
 7. ANY TRENCH LEFT VACANT (if not regrades) UTILITIES, STUMP HOLES, ETC. SHALL BE BACKFILLED WITH APPROVED SOIL, PLACED IN 6 INCH LIFTS AND COMPACTED TO 95% DENSITY IN ACCORDANCE WITH ASTM D-1557.
 8. SUBGRADE SHALL BE PROOF ROLLED WITH A LOADED DUMP TRUCK. ANY "PUMPING" OR UNSTABLE AREAS SHALL BE REMOVED AND REPLACED AS PER SPECIAL CONSTRUCTION NOTE #6. IN THE CASE OF EXCESSIVE MOISTURE, THE AREA MAY BE ALLOWED TO DRY AND RE-PROOF ROLLED.
 9. ALL FILL SOILS FOR THIS PROJECT SHALL BE AS PER SPECIAL CONSTRUCTION NOTE #5.
 10. SOILS CLASSIFIED AS MH, CH, CC OR SC WILL NOT BE ACCEPTABLE.
 11. ALL FOOTING EXCAVATIONS AND SLAB SUBGRADES SHALL BE COMPACTED TO A MINIMUM OF 95% IN ACCORDANCE WITH ASTM D-1557.
 12. SLABS ON GRADE SHOULD BE SUPPORTED BY A MINIMUM OF 4 INCHES OF GRANULAR FREE DRAINING GRAVEL OR COARSE SAND TO REMOVE MOISTURE.
 13. A VAPOR RETARDING MEMBRANE SHALL BE PLACED BETWEEN GRANULAR BASE AND CONCRETE TO PREVENT MIGRATION.

- GENERAL NOTES:
1. SEE SHEET C2 FOR LEGEND.
 2. LIMITS OF GRADING AND GRASSING ARE INDICATED ON THE SOIL EROSION AND SEDIMENT CONTROL PLANS AS "LIMITS OF DISTURBANCE".
 3. CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL EXISTING UTILITIES PRIOR TO COMMENCING OF CONSTRUCTION AND FOR AVOIDING CONFLICT WITH SAME. ANY DAMAGE TO EXISTING UTILITIES SHALL BE REPAIRED AT THE EXPENSE OF THE CONTRACTOR.
 4. ALL DISTURBED AREAS FROM NEW CONSTRUCTION ACTIVITIES WILL BE SEEDED, MULCHED, FERTILIZED AND WATERED TO PROMOTE A SUFFICIENT GROUND COVER THAT WILL PREVENT SOIL EROSION.
 5. DRAINAGE: ALL EXCAVATION SHALL BE PERFORMED SO THAT THE SITE AND THE AREA IMMEDIATELY SURROUNDING THE SITE WHICH EFFECTS THE OPERATIONS WILL BE CONTINUALLY AND EFFECTIVELY DRAINED. SURFACE WATER, GROUNDWATER, OR ANY PERCHED WATER WHICH MIGHT BE ENCOUNTERED DURING EXCAVATIONS SHALL BE REMOVED BY ANY ACCEPTABLE MEANS APPROVED BY THE ENGINEER.
 6. ELEVATIONS ARE BASED ON NAVD 88 DATUM. SEE C2 FOR ELEVATION DATUM.
 7. CONTRACTOR TO VERIFY ALL EXISTING AND PROPOSED STRUCTURE LOCATIONS (drainage, sanitary, etc.) TOPS AND DEPTHS PRIOR TO ORDERING MATERIALS OR BEGINNING CONSTRUCTION.
 8. DETENTION BASIN MAY BE ENLARGED (not deepened) TO GAIN FILL FOR CONSTRUCTION IF THE MATERIAL IS SATISFACTORY.
 9. DETENTION BASIN IS TO BE CONSTRUCTED WITH 3:1 SIDESLOPES.
 10. DETENTION BASIN IS TO BE SODDED TO PREVENT EROSION.
 11. 1 1/2" CURB AND GUTTER (if required) TO BE CONCRETE.
 12. #12 GA. WIRE SHALL BE INSTALLED ABOVE ALL STORM PIPES AT 1' TO 2' FEET ABOVE PIPE.
 13. ALL STORM PIPE JOINTS SHALL BE WRAPPED WITH FILTER FABRIC.
 14. SEE UTILITY PLAN FOR PIPE SEPARATION NOTES.
 15. PARKING AREA IS TO BE PRIVATELY OWNED AND MAINTAINED.

- PAVING SURFACE LEGEND
- | | |
|---------------------|-------|
| HEAVY DUTY | +++++ |
| STANDARD DUTY | +++ |
| CRUSHER RUN | ++ |
| CONCRETE | — |
| STABILIZED EARTH | — |
| GDOT PAVING | — |
| FUTURE BUILDING | — |
| DUMPED STON RIP-RAP | — |

- Survey Information:
1. Survey information: Gardner Surveying
 2. Date of Original Survey: May, 2024
 3. Datum: NAVD 88

- LANDSCAPE AND UTILITY BOND NOTES:
1. LANDSCAPE AND UTILITY BONDS THAT ARE REQUIRED BY THE CITY OF POOLER ARE TO BE SUPPLIED AND MAINTAINED BY THE SITE CONTRACTOR.

- PARKING OWNERSHIP NOTES:
1. PARKING AREAS ARE TO BE PRIVATELY OWNED AND MAINTAINED.

REVISIONS

NO. 1

DATE

BY

DESCRIPTION

BOSWELL DESIGN SERVICES, INC.

OFFICE: 4700 EAST HIGHWAY 88
Unit N, Suite 1
SAVANNAH, GEORGIA 31410
912 - 897 - 6932
LAHBOS@bellsouth.net

CHECKED

DRAWN

DESIGNED

DATE

JOB NO.

SCALE

AS SHOWN


MOSAIC GALLERIA
125 HIGH AVENUE
POOLER, GEORGIA 31322
MOSAIC FIVE, LLC
BEAUFORT, SOUTH CAROLINA

CONTACT A MINIMUM OF 72 HOURS PRIOR TO ISSUING

UTILITIES PROTECTION CENTER
1-800-282-7411

GEORGIA
Professional Engineer
No. 28372
10-6-25
MARK A. BOSWELL

DRAWING NUMBER
C-5
5 OF 28 SHEETS



APPROACH NOTES :

1. DRIVEWAY SUBGRADE SHALL BE COMPACTED TO 100% AS PER SECTION 02200, PART 3.01 B.
2. MINIMUM COMPRESSIVE STRENGTH SHALL BE 5,000 psi AS PER SECTION 03300, PART 3.2 IN CITY OF SAVANNAH R.O.W. AND ELSEWHERE.

DUMPSTER PAD AND APPROACH PAD DETAIL



SPECIAL ORDINANCE NOTE:

I. IN CASE OF CONFLICT BETWEEN THESE PLANS AND THE CITY OF POOLER'S ORDINANCES STANDARDS, SPECIFICATIONS OR DETAILS, THE CITY OF POOLER, STANDARDS ARE TO TAKE PRECEDENCE.

SPECIAL CONSTRUCTION NOTE:

IF THE CONTRACTOR KNOWS OR CAN REASONABLY BE EXPECTED TO HAVE KNOWN OF AN ERROR, DISCREPANCY OR CONFLICT IN THE PLANS, SPECIFICATIONS OR CONSTRUCTION STAKING AND FAILS TO REPORT THE PROBLEM PRIOR TO CONSTRUCTION, HE SHALL NOT BE ENTITLED TO COMPENSATION FOR ANY WORK OR EXPENSE INCURRED BY HIM FOR WORK REQUIRED TO BE RE-CONSTRUCTED BECAUSE OF SAID ERROR, DISCREPANCY OR CONFLICT.

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
---	---	---	---	---	---	---	---	---	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	-----

BOSWELL DESIGN SERVICES, INC.
OFFICE • 4700 EAST HIGHWAY 90



MAILING : 103 NASSAU DRIVE
SAVANNAH, GEORGIA 31410
912 - 897 - 6932
LAHBOS@Bellsouth.net



---	MAB	---
DATE : OCT. 6, 2025		
JOB NO. ---		
SCALE: as shown		

MOSAIC GALLERY
125 HIGH AVENUE
POOLER, GEORGIA 31322
FOR
MOSAIC FIVE, LLC
BEAUFORT, SOUTH CAROLINA


DETAILS



DRAWING NUMBER


C-13

3 OF 28 SHEETS




Sd4-C Detail

Sd4



Sd4-C Detail

Sd4



"I certify under penalty of law that this Plan was prepared after a site visit to the locations described herein by myself or my authorized agent, under my supervision."

"I certify that the permittee's Erosion, Sedimentation and Pollution Control Plan provides for an appropriate and comprehensive system of best management practices required by the Georgia Water Quality Control Act and the document: "Manual for Erosion and Sediment Control in Georgia" (Manual) published by the Georgia Soil and Water Conservation Commission as of January 1 of the year in which the land-disturbing activity was permitted, provides for the sampling of the receiving water(s) or the sampling of the stormwater outfalls and that the designed system of best management practices and sampling methods is expected to meet the requirements contained in the General NPDES Permit No. GAR100001."

Mark Boswell

CERTIFIED BY: Mark A. Boswell
Level II Certification No. 2104

STREAM BUFFER ENCROACHMENT NOTES:

1. NEW STRUCTURES ON THIS PROJECT DO NOT ENCROACH IN THE 25 OR 50 FOOT STREAM BUFFER.
2. NON-EXEMPT ACTIVITIES SHALL NOT BE CONDUCTED WITHIN THE 25 OR 50 FOOT UNDISTURBED STREAM BUFFERS AS MEASURED FROM THE POINT OF WRESTED VEGETATION OR WITHIN 25 FEET OF THE COASTAL MARSHLAND BUFFER AS MEASURED FROM THE JURISDICTIONAL DETERMINATION LINE WITHOUT FIRST ACQUIRING THE NECESSARY VARIANCES AND PERMITS.

SPECIAL ORDINANCE NOTE:

1. IN CASE OF CONFLICT BETWEEN THESE PLANS AND THE CITY OF POOLER'S ORDINANCES STANDARDS, SPECIFICATIONS OR DETAILS, THE CITY OF POOLER STANDARDS ARE TO TAKE PRECEDENCE.


SPECIAL CONSTRUCTION NOTE:


IF THE CONTRACTOR KNOWS OR CAN REASONABLY BE EXPECTED TO HAVE KNOWN OF AN ERROR, DISCREPANCY OR CONFLICT IN THE PLANS, SPECIFICATIONS OR CONSTRUCTION STAKING AND FAILS TO REPORT THE PROBLEM PRIOR TO CONSTRUCTION, HE SHALL NOT BE ENTITLED TO COMPENSATION FOR ANY WORK OR EXPENSE INCURRED BY HIM FOR WORK REQUIRED TO BE RE-CONSTRUCTED BECAUSE OF SAID ERROR, DISCREPANCY OR CONFLICT.

LEVEL II
CERTIFICATION
NO. 2104
ISSUED 11-5-05
EXPIRES 11-15-26

SCALE: 1" = 30'

REVISIONS	
BOSWELL DESIGN SERVICES, INC. OFFICE: 4700 EAST HIGHWAY 80 Unit N, Suite 1 MAILING: 103 NASSAU DRIVE SAVANNAH, GEORGIA 31410 912 - 897 - 6932 LAHBOS@bellsouth.net	
CHIEF DESIGNED	DATE: OCT 6, 2025
DRAWN MMS	JOB NO.
CHECKED	SCALE: as shown
MOSAIC GALLERIA 125 HIGH AVENUE POOLER, GEORGIA 31322 MOSAIC FIVE, LLC BEAUFORT, SOUTH CAROLINA	
SOIL EROSION AND SEDIMENT CONTROL PLAN - PHASE I	
CONTACT A MINIMUM OF 72 HOURS PRIOR TO DIGGING	
UTILITIES PROTECTION CENTER 1-800-282-7411	
GEORGIA REGISTERED PROFESSIONAL ENGINEER No. 28372 O-G-25 MARK A. BOSWELL	
DRAWING NUMBER C-15	
15 OF 28 SHEETS	





"I certify that the permittee's Erosion, Sedimentation and Pollution Control Plan provides for an appropriate and comprehensive system of best management practices required by the Georgia Water Quality Control Act and the document, "Manual for Erosion and Sediment Control in Georgia" (Manual published by the Georgia Soil and Water Conservation Commission as of January 1 of the year in which the land-disturbing activity was permitted, provides for the sampling of the receiving water(s) or the sampling of the stormwater outfalls and that the designed system of best management practices and sampling methods is expected to meet the requirements contained in the General NPDES Permit No. GAR 100001."

CERTIFIED BY : Mark A. Boswell
Level II Certification No. 2104

[illegible]

BOSWELL DESIGN SERVICES, INC.
OFFICE: 4700 EAST HIGHWAY 80
Unit N, Suite 1
MAILING: 103 NASSAU DRIVE
SAVANNAH, GEORGIA 31410
912 • 897 • 6932
LAHBOS@bellsouth.net




DESIGNED ---	DRAWN MAB	CHECKED ---
DATE: OCT. 6, 2025		
JOB NO. ---		
SCALE: as shown		

MOSAIC GALLERY
125 HIGH AVENUE
POOLER, GEORGIA 31322
FOR
MOSAIC FIVE, LLC
BEAUFORT, SOUTH CAROLINA

CONTACT A MINIMUM OF 72 HOURS
PRIOR TO DIGGING



UTILITIES PROTECTION CENTER
1-800-282-2411



DRAWING NUMBER

C-17

17 OF 28 SHEETS

STREAM BUFFER ENCROACHMENT NOTES :

1. NEW STRUCTURES ON THIS PROJECT DO NOT ENCROACH IN THE 25 OR 50 FOOT STREAM BUFFER.
2. NON-EXEMPT ACTIVITIES SHALL NOT BE CONDUCTED WITHIN THE 25 OR 50 FOOT UNDISTURBED STREAM BUFFERS AS MEASURED FROM THE POINT OF WRESTED VEGETATION OR WITHIN 25 FEET OF THE COASTAL MARSHLAND BUFFER AS MEASURED FROM THE JURISDICTIONAL DETERMINATION LINE WITHOUT FIRST ACQUIRING THE NECESSARY VARIANCES AND PERMITS.


SPECIAL ORDINANCE NOTE :
I. IN CASE OF CONFLICT BETWEEN THESE PLANS AND THE CITY OF POOLER'S ORDINANCES STANDARDS, SPECIFICATIONS OR DETAILS, THE CITY OF POOLER, STANDARDS ARE TO TAKE PRECEDENCE.

EQUIVALENT CONTROLS NOTE :
I. SINCE THE DETENTION IS AN EXTENDED DISTANCE DOWNSTREAM FROM THE PROPOSED SITE, EQUIVALENT CONTROLS MAY BE USED FOR PHASES II AND III.

SPECIAL CONSTRUCTION NOTE:

IF THE CONTRACTOR KNOWS OR CAN REASONABLY BE EXPECTED TO HAVE KNOWN OF AN ERROR, DISCREPANCY OR CONFLICT IN THE PLANS, SPECIFICATIONS OR CONSTRUCTION STAKING AND FAILS TO REPORT THE PROBLEM PRIOR TO CONSTRUCTION, HE SHALL NOT BE ENTITLED TO COMPENSATION FOR ANY WORK OR EXPENSE INCURRED BY HIM FOR WORK REQUIRED TO BE RE-CONSTRUCTED BECAUSE OF SAID ERROR, DISCREPANCY OR CONFLICT.

LEVEL II
CERTIFICATION
NO. 2104
ISSUED 11-5-05
EXPIRES 11-15-26



SOIL EROSION AND SEDIMENT CONTROL PLAN - PHASE III
1" = 30'

1. NEW STRUCTURES ON THIS PROJECT DO NOT ENCRoACH IN THE 25 OR 50 FOOT STREAM BUFFER.
2. NON-EXEMPT ACTIVITIES SHALL NOT BE CONDUCTED WITHIN THE 25 OR 50 FOOT UNDISTURBED STREAM BUFFERS AS MEASURED FROM THE POINT OF WRESTED VEGETATION OR WITHIN 25 FEET OF THE COASTAL MARSHLAND BUFFER AS MEASURED FROM THE JURISDICTIONAL DETERMINATION LINE WITHOUT FIRST ACQUIRING THE NECESSARY VARIANCES AND PERMITS.

LEVEL II
CERTIFICATION
NO. 2104
ISSUED 11-5-05
EXPIRES 11-15-26

REVISIONS

BOSWELL DESIGN SERVICES, INC.

OFFICE : 4700 EAST HIGHWAY 80
Unit N, Suite 1
MAILING : 103 NASSAU DRIVE
SAVANNAH, GEORGIA 31410
912 - 897 - 6932
LAHBOS@Bellsouth.net

DESIGNED ---	DRAWN MAB	CHECKED ---
-----------------	--------------	----------------

DATE : OCT. 6, 2025

JOB NO. --

SCALE: as shown


MOSAIC GALLERIA
125 HIGH AVENUE
POOLER, GEORGIA 31322
FOR
MOSAIC FIVE, LLC
BEAUFORT, SOUTH CAROLINA

EXCAVATED INLET SEDEIMENT TRAP DETAILS

CONTACT A MINIMUM OF 72 HOURS
PRIOR TO DIGGING



UTILITIES PROTECTION CENTER
1-800-282-7411



DRAWING NUMBER

C-18

18 OF 28 SHEETS

DEFINITION

PURPOSE

INSTALLATION

INSTALLATION

- Install according to approved plan, if shown.
- Do not install where vehicular traffic will be affected.
- Install at or around all storm drain drop inlets that receive runoff from disturbed areas.
- Construct on natural ground surface, excavated surface, or on machine compacted fill.


Excavated Sediment Traps

- Minimum of 1.5 feet of sediment storage in excavated sediment traps.
- Must be self-draining unless otherwise protected.

"I certify that the permittee's Erosion, Sedimentation and Pollution Control Plan provides for appropriate and comprehensive system of best management practices required by the Georgia Water Quality Control Act and the document "Manual for Erosion and Sediment Control in Georgia" (Manual) published by the Georgia Soil and Water Conservation Commission as of January 1 of the year in which the land-disturbing activity was permitted, provides for the sampling of the receiving water(s) or the sampling of the stormwater outfalls and that the designed system of best management practices and sampling methods is expected to meet the requirements contained in the General NPDES Permit No. GAR 100001."

CERTIFIED BY : Mark A. Boswell
Level II Certification No. 2104

Figure 1. Fabric and supporting Frame for Inlet Protection (Sd2-F)



SD2-F EXCAVATED SEDIMENT TRAP DETAIL
NOT TO SCALE

I. IN CASE OF CONFLICT BETWEEN THESE PLANS AND THE CITY OF POOLER'S ORDINANCES STANDARDS, SPECIFICATIONS OR DETAILS, THE CITY OF POOLER, STANDARDS ARE TO TAKE PRECEDENCE.

SPECIAL CONSTRUCTION NOTE:

IF THE CONTRACTOR KNOWS OR CAN REASONABLY BE EXPECTED TO HAVE KNOWN OF AN ERROR, DISCREPANCY OR CONFLICT IN THE PLANS, SPECIFICATIONS OR CONSTRUCTION STAKING AND FAILS TO REPORT THE PROBLEM PRIOR TO CONSTRUCTION, HE SHALL NOT BE ENTITLED TO COMPENSATION FOR ANY WORK OR EXPENSE INCURRED BY HIM FOR WORK REQUIRED TO BE RE-CONSTRUCTED BECAUSE OF SAID ERROR, DISCREPANCY OR CONFLICT.

SOIL EROSION & SEDIMENTATION CONTROL NOTES

1. NARRATIVE: THE EXISTING SITE IS VACANT AND THE GROUND IS GENERALLY FLAT WITH SLOPES BETWEEN 0 AND FOUR PERCENT WITH FEW TREES. THE PROPOSED DEVELOPMENT WILL BE TWO NEW RETAIL BUILDINGS AND TWO NEW RESTAURANTS AND WILL HAVE PAVING, GRADING, DRAINAGE AND UTILITIES. DETENTION WILL BE ACHIEVED BY UTILIZING THE EXISTING PARK POND. THE TOTAL SITE IS APPROXIMATELY 1.9 ACRES WITH THE DISTURBED AREA BEING APPROXIMATELY 2.5 ACRES.

2. DEVELOPER / OWNER : MOSAIC FIVE, LLC
D.J. DESAI (CONTACT)
P.O. BOX 6465
BEAUFORT, SOUTH CAROLINA 29906

PRIMARY PERMITTEE EMAIL : DJDESAI@HDCOMPANIES.COM

3. 24 HOUR CONTACT : D.J. DESAI
843-379-9405

4. ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IN CONFORMANCE WITH THE CURRENT STATE SOIL AND WATER CONSERVATION COMMITTEE OF GEORGIA "MANUAL FOR EROSION CONTROL IN GEORGIA.

5. PRIOR TO ANY OTHER CONSTRUCTION, STABILIZED CONSTRUCTION EXITS SHALL BE CONSTRUCTED AT EACH POINT OF ENTRY TO OR EXIT FROM THE SITE. ALL ENTRANCES TO THE SITE WHICH ARE NOT PROTECTED SHALL BE BARRICADED.

6. IMMEDIATELY AFTER THE ESTABLISHMENT OF CONSTRUCTION EXITS, ALL PERIMETER EROSION CONTROL DEVICES AND STORM WATER MANAGEMENT DEVICES SHALL BE INSTALLED PRIOR TO ANY OTHER CONSTRUCTION.

7. ADDITIONAL EROSION CONTROL DEVICES SHALL BE INSTALLED IMMEDIATELY AFTER GROUND DISTURBANCE OCCURS. THE LOCATION OF SOME OF THE EROSION CONTROL DEVICES MAY HAVE TO BE ALTERED FROM THAT SHOWN ON THE PLANS IF DRAINAGE PATTERNS DURING CONSTRUCTION ARE DIFFERENT FROM THE FINAL PROPOSED DRAINAGE PATTERNS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO ACCOMPLISH EROSION CONTROL FOR ALL DRAINAGE PATTERNS CREATED AT VARIOUS STAGES DURING ANY PHASE OF CONSTRUCTION. ANY DIFFICULTY IN CONTROLLING EROSION DURING ANY PHASE OF CONSTRUCTION SHALL BE REPORTED TO THE ENGINEER IMMEDIATELY !

8. THE LOCATIONS OF EROSION CONTROL DEVICES SHALL BE ADJUSTED AS CONSTRUCTION PROGRESSES IN ORDER TO MAINTAIN A FUNCTIONING EROSION CONTROL SYSTEM.

9. THE FAILURE OF ANY EROSION CONTROL DEVICE TO FUNCTION AS INTENDED, FOR ANY REASON, SHALL BE REPORTED TO THE ENGINEER IMMEDIATELY !

10. EROSION CONTROL DEVICES SHALL BE INSPECTED AFTER EACH RAINFALL EVENT AND AT LEAST DAILY DURING PROLONGED PERIODS OF CONTINUOUS RAINFALLS.

11. EROSION CONTROL DEVICES SHALL BE CLEANED WHEN THEY BECOME HALF FILLED WITH SEDIMENT.

12. EROSION CONTROL DEVICES SHALL BE REPAIRED AS NECESSARY TO MAINTAIN A FUNCTIONING EROSION CONTROL SYSTEM.

13. EROSION CONTROL DEVICES SHALL BE MAINTAINED UNTIL PERMANENT COVER IS ESTABLISHED AND THEN REMOVED SO THAT DRAINAGE FROM THE SITE IS NOT IMPAIRED.

14. STORM WATER DETENTION DEVICES SHALL BE CLEANED AS SPECIFIED ABOVE AND AFTER PERMANENT GROUND COVER HAS BEEN ESTABLISHED.

15. ANY DISTURBED AREA LEFT EXPOSED FOR A PERIOD GREATER THAN 14 DAYS SHALL BE STABILIZED WITH TEMPORARY SEEDING.

16. ANY DISTURBED AREAS WITH SLOPES 2:1 OR FLATTER WHICH ARE NOT STABILIZED BY ANY OTHER MEASURES SHALL BE SEEDED AS SPECIFIED IN "PERMANENT SEEDING".

17. VEGETATIVE METHODS:
A VEGETATIVE COVER SHALL BE ESTABLISHED AND MAINTAINED OVER ALL FINAL GRADING AND OTHER DISTURBED AREAS OF THE SITE. SEE COASTAL PLAIN VEGETATIVE COVERS FOR AN OUTLINE OF THE ESTABLISHMENT OF VEGETATIVE COVERS.

WEEKLY INSPECTION OF THE GRASS COVER SHALL BE PERFORMED TO IDENTIFY AREAS REQUIRING RE-ESTABLISHMENT OF GRASS.

LIME RATE: 1 TO 2 TONS PER ACRE
FERTILIZER: 1500 POUNDS OF 6-12-12 PER ACRE

18. MULCH:
MULCH SHALL BE UNCHOPPED, UNROTTED, SMALL GRAIN DRY STRAW APPLIED AT A RATE OF 2 TONS PER ACRE. MULCH MATERIAL SHALL BE RELATIVELY FREE FROM ALL KINDS OF WEEDS AND SHALL BE FREE OF PROHIBITED NOXIOUS WEEDS WHICH ARE AS FOLLOWS : CANADA THISTLE, JOHNSONGRASS AND QUACKGRASS. SPREAD MULCH MECHANICALLY OR UNIFORMLY BY HAND. MULCH ANCHORING SHALL BE ACCOMPLISHED IMMEDIATELY AFTER MULCH PLACEMENT TO MINIMIZE LOSS BY WIND OR WATER. THIS MAY BE DONE BY PEG AND TWINE METHOD, MULCH ANCHORING TOOL, NETTING OR LIQUID MULCH BINDERS.

19. SOIL TYPE: THE SOILS IN THIS AREA HAVE BEEN CLASSIFIED BY THE SOIL CONSERVATION SERVICE AS : Oj (Ocilla Complex) and Waf (Wahee Sandy Loam)Waf (Wahee Sandy Loam).

20. THIS DEVELOPMENT IS WITHIN MINIMAL ZONING AREA "X" ACCORDING TO F.I.R.M. COMMUNITY PANEL NUMBER 13051C0109G, MAP REVISED 8-16-18.

21. THIS SITE IS IN FLOOD ZONE "X" AND IS NOT LOCATED WITHIN THE 100 YEAR FLOOD ZONE.

SPECIAL NOTES:

1. THE ESCAPE OF SEDIMENT FROM THE SITE SHALL BE PREVENTED BY THE INSTALLATION OF EROSION AND SEDIMENT CONTROL MEASURES AND PRACTICES PRIOR TO OR CONCURRENT WITH LAND DISTURBING ACTIVITIES.

2. THE INSTALLATION OF EROSION CONTROL MEASURES AND PRACTICES SHALL BE INSTALLED PRIOR TO OR CONCURRENT WITH LAND DISTURBING ACTIVITIES.

3. EROSION CONTROL MEASURES WILL BE MAINTAINED AT ALL TIMES. IF FULL IMPLEMENTATION OF THE APPROVED PLAN DOES NOT PROVIDE FOR EFFECTIVE EROSION CONTROL, ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE SEDIMENT SOURCE.

4. CITY OF POOLER PERSONNEL SHALL HAVE THE RIGHT TO INSPECT STORMWATER FACILITIES AT ALL TIMES.

5. STATE WATERS DO NOT EXIST ON THIS PROPERTY.

6. FRESH WATER WETLANDS DO NOT EXIST ON THIS PROPERTY.

7. THE EROSION AND SEDIMENT CONTROL PLAN DESIGNER HAS VISITED THE SITE PRIOR TO DESIGN OF THE E & SC PLANS.

8. THE RECEIVING WATERS FOR THIS PROJECT IS THE EXISTING POOLER DRAINAGE SYSTEM, PARK POND, SEVERAL UN-NAMED CONVEYANCES, OGEECHEE RIVER AND ULTIMATELY THE ATLANTIC OCEAN.

9. ANY DISTURBANCE AREA LEFT EXPOSED FOR A PERIOD GREATER THAN 14 DAYS SHALL BE STABILIZED WITH TEMPORARY SEEDING.

10. AMENDMENTS OR REVISIONS TO THE ES & PC PLAN WHICH HAVE A HYDRAULIC EFFECT ON THE PROJECT MUST BE APPROVED BY THE DESIGN ENGINEER.

CLEARING NOTES:

1. ALL ELEVATIONS ARE BASED ON 88 NAVD DATUM.

2. CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ALL EXISTING UNDERGROUND UTILITIES PRIOR TO BEGINNING CONSTRUCTION ACTIVITIES AND FOR AVOIDING ALL CONFLICTS WITH SAME. ANY DAMAGE TO EXISTING UTILITIES SHALL BE REPAIRED AT THE EXPENSE OF THE CONTRACTOR.

3. ALL WORK SHALL BE IN COMPLIANCE WITH THE STATE SOIL AND WATER CONSERVATION COMMITTEE'S "MANUAL FOR EROSION AND SEDIMENTATION CONTROL IN GEORGIA. ALL SEDIMENT CONTROL FEATURES SHALL BE MAINTAINED ON A REGULAR BASIS AND SHALL BE REMOVED BY THE CONTRACTOR UPON ACCEPTANCE OF THE SITE BY THE OWNER. SEE LAND DISTURBING PLAN.

4. ALL DISTURBED AREAS AND PROPOSED EARTH GRADING NOT TO BE COVERED BY OTHER SURFACES SHALL BE GRASSED AS DESCRIBED ON THE LAND DISTURBING ACTIVITY PLAN.

5. EGRESS FROM THE SITE WILL BE SUCH THAT ALL VEHICLES MUST TRAVERSE CONSTRUCTION EXITS TO REMOVE MUD FROM TIRES BEFORE ENTERING ANY PAVED PUBLIC HIGHWAY.

6. BALES OF HAY, STRAW OR SILT FENCE SHALL BE PLACED AROUND ALL STORM INLETS TO PREVENT SEDIMENT FROM ENTERING NEW PIPE OR DRAINAGE WAYS DURING CONSTRUCTION. THESE MEASURES ARE TEMPORARY.

7. THE SITE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING POSITIVE DRAINAGE OF ALL AREAS WITHIN THE PROJECT SITE INCLUDING RIGHTS-OF-WAYS, EASEMENTS AND LOTS. THE CONTRACTOR SHALL PROVIDE THE NECESSARY FILL AND OR GRADING TO MEET THE FINISHED PLAN GRADES AND ELIMINATE ANY AND ALL AREAS WHICH ARE LOW AND DO NOT DRAIN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ENSURING PROPER DRAINAGE OF ANY AREAS WHICH ARE CHANGED AS A RESULT OF FIELD ADJUSTMENTS TO THE CONSTRUCTION PLANS.

8. THE CONTRACTOR WILL NOT BEGIN CLEARING OR ANY CONSTRUCTION ACTIVITY UNTIL THE APPROPRIATE PERMITS HAVE BEEN ISSUED.

9. IF REQUIRED, TREE PROTECTION BARRICADES SHALL BE INSTALLED PRIOR TO ANY CLEARING ACTIVITY AND MAINTAINED UNTIL INSTRUCTED BY OWNER OR ENGINEER TO REMOVE THEM.

10. THE CONTRACTOR SHALL TAKE SPECIAL CARE TO AVOID DAMAGE TO TREES AND ROOT SYSTEMS WHILE WORKING WITHIN TREE PROTECTION BARRICADES. THE CONTRACTOR SHALL NOT WORK WITHIN TREE PROTECTION BARRICADES WITHOUT A REPRESENTATIVE FROM THE OWNER OR ENGINEER PRESENT.

11. PRUNING OF TREE LIMBS, BRANCHES AND ROOTS OF TREES WHICH ARE WITHIN TREE PROTECTION BARRICADES SHALL BE DONE IN CONFORMANCE WITH SPECIFICATIONS AND RECOMMENDATIONS OF THE "NATIONAL ARBORIST ASSOCIATION" (N.A.A.) IN "PRUNING STANDARDS FOR SHADE TREES". ANY VARIATION FROM THE RECOMMENDATION OF THE N.A.A. SHALL BE APPROVED BY THE OWNER IN WRITING PRIOR TO ANY PRUNING.

12. LIMITS OF GRADING AND GRASSING ARE INDICATED ON PLANS AS "LIMITS OF DISTURBANCE".

13. ALL DISTURBED AREAS FROM NEW CONSTRUCTION ACTIVITIES WILL BE SEEDED, MULCHED, FERTILIZED AND WATERED TO PROMOTE A SUFFICIENT GROUND COVER THAT WILL PREVENT SOIL EROSION. SUFFICIENT COVERAGE SHALL BE AS SPECIFIED IN "EROSION CONTROL GRASSING".





14. DRAINAGE: ALL EXCAVATION SHALL BE PERFORMED SO THAT THE SITE AND THE AREA IMMEDIATELY SURROUNDING THE SITE WHICH EFFECTS THE OPERATIONS WILL BE CONTINUALLY AND EFFECTIVELY DRAINED. SURFACE WATER, GROUNDWATER, OR ANY PERCHED WATER WHICH MIGHT BE ENCOUNTERED DURING EXCAVATIONS SHALL BE REMOVED BY ANY ACCEPTABLE MEANS APPROVED BY THE ENGINEER.

TENTATIVE ACTIVITY SCHEDULE

	2025						
	APR	MAY	JUNE	JULY	AUG	SEPT	
DEMOLITION, CLEARING, GRUBBING							
INSTALLATION OF SEDIMENT CONTROLS AND TREE PROTECTION BARRICADES							
TEMPORARY GRASSING							
SITE GRADING							
UTILITY INSTALLATION							
BUILDING CONSTRUCTION							
PERMANENT GRASSING							
PAVING							
MAINTENANCE OF SEDIMENT CONTROL							
REMOVAL OF SEDIMENT CONTROL							

SITE DATA

ZONE....."X"
TOTAL ACREAGE.....1.9 ACRES
DISTURBED ACREAGE.....2.5 ACRES (OFFSITE + R/W)
S.C.S. SOIL SURVEY MAP AS PER WEB SOIL SURVEY



"I certify under penalty of law that this Plan was prepared after a site visit to the locations described herein by myself or my authorized agent, under my supervision."



"I certify that the permittee's Erosion, Sedimentation and Pollution Control Plan provides for an appropriate and comprehensive system of best management practices required by the Georgia Water Quality Control Act and the document "Manual for Erosion and Sediment Control in Georgia" (Manual) published by the Georgia Soil and Water Conservation Commission as of January 1 of the year in which the land-disturbing activity was permitted, provides for the sampling of the receiving water(s) or the sampling of the stormwater outfalls and that the designed system of best management practices and sampling methods is expected to meet the requirements contained in the General NPDES Permit No. GAR100001."

Mark A. Boswell
Level II Certification No. 2104

STREAM BUFFER ENCROACHMENT NOTES :

1. NEW STRUCTURES ON THIS PROJECT DO NOT ENCRACH IN THE 25 OR 50 FOOT STREAM BUFFER.
2. NON-EXEMPT ACTIVITIES SHALL NOT BE CONDUCTED WITHIN THE 25 OR 50 FOOT UNDISTURBED STREAM BUFFERS AS MEASURED FROM THE POINT OF WRESTED VEGETATION OR WITHIN 25 FEET OF THE COASTAL MARSHLAND BUFFER AS MEASURED FROM THE JURISDICTIONAL DETERMINATION LINE WITHOUT FIRST ACQUIRING THE NECESSARY VARIANCES AND PERMITS.

WEIGHTED RUN-OFF COEFFICIENTS :
PRE-DEVELOPED = 74
POST-DEVELOPED = 89



SPECIAL ORDINANCE NOTE :

LEVEL II
CERTIFICATION
NO. 2104
ISSUED 11-5-05
EXPIRES 11-15-26

REVISIONS	DATE	BY	REVISION
1	2025/06/03	REVISED	PER CITY REVIEW COMMENTS

BOSWELL DESIGN SERVICES, INC.
OFFICE: 4700 EAST HIGHWAY 80
Unit N, Suite 1
MAILING: 103 NASSAU DRIVE
SAVANNAH, GEORGIA 31410
912 - 897 - 6932
LAHBOS@bellsouth.net

CHECKED	DATE	BY	REVISION
1	2025	10/06/25	1

MOSAIC GALLERIA
125 HIGH AVENUE
POOLER, GEORGIA 31322
MOSAIC FIVE, LLC
BEAUFORT, SOUTH CAROLINA

NOTES AND DETAILS

CONTACT A MINIMUM OF 72 HOURS
PRIOR TO DIGGING

UTILITIES PROTECTION CENTER
1-800-282-7411

7 DAY INSPECTION NOTE :

The design professional is to inspect the installation of the initial sediment storage requirements and perimeter control BMP's. The design professional must be retained by the primary permittee to conduct a site inspection within seven (7) days after the the installation of the initial sediment storage requirements and perimeter control BMP's. The design professional must report the results of the inspection to the primary permittee within seven (7) days and the primary must correct all deficiencies identified in the report within two (2) business days after receiving the report (unless additional time is needed due to adverse weather). The primary permittee may use an alternate design professional to conduct the BMP inspection, provided that they make a written request to EPD to change from the design professional who developed the plan and EPD has agreed.

DESIGN PROFESSIONAL 7 DAY VISIT CERTIFICATION

Date of Inspection :

I certify the site was in compliance with the ES&PC Plan on the date of inspection.

Mark Boswell

2104

GSWC LEVEL II DESIGN PROFESSIONAL

CERTIFICATION #

Inspection revealed the following discrepancies from the ES&PC Plan.

These deficiencies must be addressed immediately and a re-inspection scheduled. Work shall not proceed on the site until design Professional Certification is obtained.

PRODUCT SPECIFIC PRACTICES

- Petroleum Based Products** – Containers for products such as fuels, lubricants and tars will be inspected daily for leaks and spills. This includes on-site vehicle and machinery daily inspections and regular preventative maintenance of such equipment. Equipment maintenance areas will be located away from state water, natural drains and storm water drainage inlets. In addition, temporary fueling tanks shall have a secondary containment liner to prevent/minimize site contamination. Discharge of oils, fuels, and lubricants is prohibited. Proper disposal methods will include collection in a suitable container and disposal as required by local and State regulations.
- Points / Finishes / Solvents** – All products will be stored in tightly sealed original containers when not in use. Excess product will not be discharged to the storm water collection system. Excess product, materials used with these products and product containers will be disposed of according to manufacturer's specifications and recommendations.
- Concrete Truck Washing**
 - Coordinate with site superintendent to excavate a pit deep enough to contain the wash down water.
 - Back equipment into pit.
 - Wash down only the chute hopper and rear of the vehicle. DO NOT WASH OUT DRUM.
 - Make sure wash down water goes into and stays in the pit.
 - Coordinate with site superintendent to fill in pit and smooth out ground.
 - Never allow wash down to enter a storm system.
- Fertilizer / Herbicides** – These products will be applied at rates that do not exceed the manufacturer's specifications or above the guidelines set forth in the crop establishment or in the GSWC Manual for Erosion and Sediment Control in Georgia. Any storage of these materials will be under roof in sealed containers.
- Building Materials** – No building materials will be buried or disposed on-site. All such materials will be disposed of in proper waste disposal procedures.

APPENDIX B
Nephelometric Turbidity Unit (NTU) Tables

		Cold Water (Trout Stream)							
		Surface Water Drainage Area, square miles							
		0-4.99	5-9.99	10-24.99	25-49.99	50-99.99	100-249.99	250-499.99	500+
SITE SIZE ACRES	1.00-10	25	50	75	150	300	500	500	500
	10.01-25	25	25	50	75	150	200	500	500
	25.01-50	25	25	25	50	75	100	300	500
	50.01-100	20	25	25	35	50	75	150	300
	100.01+	20	20	25	25	25	50	60	100

		Warm Water (Supporting Warm Water Fisheries)							
		Surface Water Drainage Area, square miles							
		0-4.99	5-9.99	10-24.99	25-49.99	50-99.99	100-249.99	250-499.99	500+
SITE SIZE ACRES	1.00-10	75	150	200	400	750	750	750	750
	10.01-25	50	100	100	200	300	500	750	750
	25.01-50	50	50	100	100	200	300	750	750
	50.01-100	50	50	50	100	100	150	300	600
	100.01+	50	50	50	50	50	100	200	100

DESCRIPTION OF STORM WATER POLLUTION
DISCHARGE PREVENTION PRACTICES

1. THE FOLLOWING IS A DESCRIPTION OF THE PRACTICES TO BE USED BUT NOT LIMITED TO :
- CONSTRUCTION EXIT
 - SILT FENCING
 - TEMPORARY SEDIMENT BASINS
 - WASHDALE CHECK DAMS
 - STONE CHECK DAMS
 - STORM OUTLET PROTECTION
 - GRASSING
 - RETENTION POND
 - STORMWATER
 - DUST CONTROL
 - CONCRETE WASHDOWN PIT
 - TEMPORARY SEDIMENT TRAPS

Soil Cleanup and Control Practices

- Local, State and manufacturer's recommended methods for spill cleanup will be clearly posted and procedures will be made available to site personnel.
- Material and equipment necessary for spill cleanup will be kept in the material storage areas. Typical materials and equipment includes, but is not limited to, brooms, dustpans, mops, rags, gloves, goggles, cat litter, sand, saw dust and properly labeled plastic and metal waste containers.
- Spill prevention practices and procedures will be reviewed after a spill and adjusted as necessary to prevent future spills.
- All spills will be cleaned up immediately upon discovery. All spills will be reported as required by local, State and Federal regulations.
- FOR SPILLS THAT IMPACT SURFACE WATER (LEAVE A SHEEN ON SURFACE WATER). THE NATIONAL RESPONSE CENTER (NRC) WILL BE CONTACTED WITHIN 24 HOURS AT 1-800-424-8802.
- FOR SPILLS OF AN UNKNOWN AMOUNT, THE NATIONAL CENTER (NRC) WILL BE CONTACTED WITHIN 24 HOURS AT 1-800-424-8802.
- FOR SPILLS GREATER THAN 25 GALLONS AND NO SURFACE WATER IMPACTS, THE GEORGIA EPD WILL BE CONTACTED WITHIN 24 HOURS.
- FOR SPILLS LESS THAN 25 GALLONS AND NO SURFACE WATER IMPACTS, THE SPILL WILL BE CLEANED UP AND LOCAL AGENCIES WILL BE CONTACTED AS REQUIRED.
- The contractor shall notify the licensed professional who prepared this plan if more than 1,320 gallons of petroleum is stored onsite (this includes capacities of equipment) or if any one piece of equipment has a capacity greater than 660 gallons. The Contractor will need a Spill Prevention Containment and Countermeasures Plan prepared by that licensed professional.

SANITARY WASTES :

- A minimum of one portable sanitary unit will be provided for every ten (10) workers on the site. All sanitary waste will be collected from the portable units a minimum of one time per week by a licensed portable facility provider in complete compliance with local and state regulations.
- All sanitary waste units will be located in an area where the likelihood of the unit contributing to storm water discharge is negligible. Additional containment BMP's must be implemented, such as gravel bags or specially designed plastic skid containers around the base, to prevent wastes from contributing to storm water discharges. The location of sanitary waste units must be identified on the Erosion Control Plan Grading Phase Sheet by the contractor once the locations have been determined.
- Sanitary Sewer will be provided by Municipal Authority/Septic System at the completion of this project.

HAZARDOUS WASTES :

- All hazardous waste materials will be disposed of in the manner specified by local, state, and/or federal regulations and by the manufacturer of such products. The jobsite superintendent, who will also be responsible for seeing that these practices are followed, will instruct site personnel in these practices. Material Safety Data Sheets (MSDS's) for each substance with hazardous properties that is used on the job site will be obtained and used for the proper management of potential wastes that may result from these products. An MSDS will be posted in the immediate area where such product is stored and/or used and another copy of the MSDS will be maintained in the ESPCP file at the jobsite construction trailer office. Each employee who must handle a substance with hazardous properties will be instructed on the use of MSDS sheets and the specific information in the applicable MSDS for the product he/she is using, particularly regarding spill control techniques.
- The contractor will implement the Spill Prevention Control and Countermeasures (SPCC) Plan found within this ESPOP and will train all personnel in the proper cleanup and handling of spilled materials. No spilled, hazardous materials or hazardous wastes will be allowed to come in contact with storm water discharges. If such contact occurs, the storm water discharge will be continued on site until appropriate measures in compliance with state and federal regulations are taken to dispose of such contaminated storm water. It shall be the responsibility of the job site superintendent to properly train all personnel in the use of the SPCC plan.

4. Inspections.

a. Permittee requirements.

- Each day when any type of construction activity has taken place at a primary permittee's site, certified personnel provided by the primary permittee shall inspect: (a) all areas at the primary permittee's site where petroleum products are stored, used, or handled for spills and leaks from vehicles and equipment and (b) all locations at the primary permittee's site where vehicles enter or exit the site for evidence of off-site sediment tracking. These inspections must be conducted until a Notice of Termination is submitted.
- Measure and record rainfall within disturbed areas of the site that have not met final stabilization once every 24 hours except any non-working Saturday, non-working Sunday and non-working Federal holiday. The data collected for the purpose of compliance with this permit shall be representative of the monitored activity. Measurement of rainfall may be suspended if all areas of the site have undergone final stabilization or established a crop of annual vegetation and a seeding of target perennials appropriate for the region.
- Certified personnel (provided by the primary permittee) shall inspect the following at least once every seven (7) calendar days and within 24 hours of the end of a storm that is 0.5 inches rainfall or greater (unless such storm ends after 5:00 PM on any Friday or on any non-working Saturday, non-working Sunday or any non-working Federal holiday in which case the inspection shall be completed by the end of the next business day and/or working day, whichever occurs first): (a) disturbed areas of the primary permittee's construction site; (b) areas used by the primary permittee for storage of materials that are exposed to precipitation; and (c) structural control measures. Erosion and sediment control measures identified in the Plan applicable to the primary permittee's site shall be observed to ensure that they are operating correctly. Where discharge locations or points are accessible, they shall be inspected to ascertain whether erosion control measures are effective in preventing significant impacts to receiving water(s). For areas of a site that have undergone final stabilization or established a crop of annual vegetation and a seeding of target perennials appropriate for the region, the permittee must comply with Part IV.D.4.a.(4). These inspections must be conducted until a Notice of Termination is submitted.

- Certified personnel (provided by the primary permittee) shall inspect at least once per month during the term of this permit (i.e., until a Notice of Termination has been submitted) the areas of the site that have undergone final stabilization or established a crop of annual vegetation and a seeding of target perennials appropriate for the region. These areas shall be inspected for evidence of, or the potential for, pollutants entering the drainage system and the receiving water(s). Erosion and sediment control measures identified in the Plan shall be observed to ensure that they are operating correctly. Where discharge locations or points are accessible, they shall be inspected to ascertain whether erosion control measures are effective in preventing significant impacts to receiving water(s).

- Based on the results of each inspection, the site description and the pollution prevention and control measures identified in the Erosion, Sedimentation and Pollution Control Plan, the Plan shall be revised as appropriate not later than seven (7) calendar days following each inspection. Implementation of such changes shall be made as soon as practical but in no case later than seven (7) calendar days following each inspection.

- A report of each inspection that includes the name(s) of certified personnel making each inspection, the date(s) of each inspection, construction phase (i.e., initial, intermediate or final), major observations relating to the implementation of the Erosion, Sedimentation and Pollution Control Plan, and actions taken in accordance with Part IV.D.4.a.(5), of the permit shall be made and retained at the site or be readily available at a designated alternate location until the entire site or that portion of a construction site that has been phased has undergone final stabilization and a Notice of Termination is submitted to EPD. Such reports shall be readily available by end of the second business day and/or working day and shall identify all incidents of best management practices that have not been properly installed and/or maintained as described in the Plan. Where the report does not identify any incidents, the inspection report shall contain a certification that the best management practices are in compliance with the Erosion, Sedimentation and Pollution Control Plan. The report shall be signed in accordance with Part V.G.2. of this permit.

- Maintenance.** The Plan shall include a description of procedures to ensure the timely maintenance of vegetation, erosion and sediment control measures and other protective measures identified in the site plan.

EROSION, SEDIMENT AND POLUTION CONTROL NOTES :

- Sampling Requirements.** This permit requires the monitoring of nephelometric turbidity in receiving water(s) or outfalls in accordance with this permit. This paragraph shall not apply to any land disturbance associated with the construction of single-family homes which are not part of a subdivision or planned common development unless five (5) acres or more will be disturbed. The following procedures constitute EPD's guidelines for sampling turbidity.

a. Sampling Requirements shall include the following:

- A USGS topographic map, a topographic map or a drawing (referred to as a topographic map) that is a scale equal to or more detailed than a 1:24000 map showing the location of the site or the stand alone construction; (a) the location of all perennial and intermittent streams and other water bodies as shown on a USGS topographic map, and all other perennial and intermittent streams and other water bodies located during mandatory field verification, into which the stormwater is discharged and (b) the receiving water and/or outfall sampling locations. When the permittee has chosen to use a USGS topographic map and the receiving water(s) is not shown on the USGS topographic map, the location of the receiving water(s) must be hand-drawn on the USGS topographic map from where the stormwater(s) enters the receiving water(s) to the point where the receiving water(s) combines with the first blue line stream shown on the USGS topographic map;
- A written narrative of site specific analytical methods used to collect, handle and analyze the samples including quality control/quality assurance procedures. This narrative must include precise sampling methodology for each sampling location;
- When the permittee has determined that some or all outfalls will be sampled, a rationale must be included on the Plan for the NTU limit(s) selected from Appendix B. This rationale must include the size of the construction site, the calculation of the size of the surface water drainage area, and the type of receiving water(s) (i.e., trout stream or supporting warm water fisheries); and
- Any additional information EPD determines necessary to be part of the Plan. EPD will provide written notice to the permittee of the information necessary and the time line for submittal.

- Sample Type.** All sampling shall be collected by "grab samples" and the analysis of these samples must be conducted in accordance with methodology and test procedures established by 40 CFR Part 136 (unless other test procedures have been approved); the guidance document titled "NPDES Storm Water Sampling Guidance Document, EPA 833-B-92-001" and guidance documents that may be prepared by the EPD.

- Sample containers should be labeled prior to collecting the samples.
- Samples should be well mixed before transferring to a secondary container.
- Large mouth, well cleaned and rinsed glass or plastic jars should be used for collecting samples. The jars should be cleaned thoroughly to avoid contamination.
- Manual, automatic or rising stage sampling may be utilized. Samples required by this permit should be analyzed immediately, but in no case later than 48 hours after collection. However, samples from automatic samplers must be collected no later than the next business day after their accumulation, unless flow through automated analysis is utilized. If automatic sampling is utilized and the automatic sampler is not activated during the qualifying event, the permittee must utilize manual sampling or rising stage sampling during the next qualifying event. Dilution of samples is not required. Samples may be analyzed directly with a properly calibrated turbidimeter. Samples are not required to be cooled.
- Sampling and analysis of the receiving water(s) or outfalls beyond the minimum frequency stated in this permit must be reported to EPD as specified in Part IV.E.

c. Sampling Points.

- For construction activities the primary permittee must sample all receiving water(s), or all outfall(s), or a combination of receiving water(s) and outfall(s). Samples taken for the purpose of compliance with this permit shall be representative of the monitored activity and representative of the water quality of the receiving water(s) and/or the stormwater outfalls using the following minimum guidelines:
 - The upstream sample for each receiving water(s) must be taken immediately upstream of the confluence of the first stormwater discharge from the permitted activity (i.e., the discharge farthest upstream at the site) but downstream of any other stormwater discharges not associated with the permitted activity. Where appropriate, several upstream samples from across the receiving water(s) may need to be taken and the arithmetic average of the turbidity of these samples used for the upstream turbidity value.

Sedimentation and Pollution Control Plan. The report shall be signed in accordance with Part V.G.2. of this permit.

- Maintenance.** The Plan shall include a description of procedures to ensure the timely maintenance of vegetation, erosion and sediment control measures and other protective measures identified in the site plan.

- Sampling Requirements.** This permit requires the monitoring of nephelometric turbidity in receiving water(s) or outfalls in accordance with this permit. This paragraph shall not apply to any land disturbance associated with the construction of single-family homes which are not part of a subdivision or planned common development unless five (5) acres or more will be disturbed. The following procedures constitute EPD's guidelines for sampling turbidity.

a. Sampling Requirements shall include the following:

- A USGS topographic map, a topographic map or a drawing (referred to as a topographic map) that is a scale equal to or more detailed than a 1:24000 map showing the location of the site or the stand alone construction; (a) the location of all perennial and intermittent streams and other water bodies as shown on a USGS topographic map, and all other perennial and intermittent streams and other water bodies located during mandatory field verification, into which the stormwater is discharged and (b) the receiving water and/or outfall sampling locations. When the permittee has chosen to use a USGS topographic map and the receiving water(s) is not shown on the USGS topographic map, the location of the receiving water(s) must be hand-drawn on the USGS topographic map from where the stormwater(s) enters the receiving water(s) to the point where the receiving water(s) combines with the first blue line stream shown on the USGS topographic map;
- A written narrative of site specific analytical methods used to collect, handle and analyze the samples including quality control/quality assurance procedures. This narrative must include precise sampling methodology for each sampling location;
- When the permittee has determined that some or all outfalls will be sampled, a rationale must be included on the Plan for the NTU limit(s) selected from Appendix B. This rationale must include the size of the construction site, the calculation of the size of the surface water drainage area, and the type of receiving water(s) (i.e., trout stream or supporting warm water fisheries); and
- Any additional information EPD determines necessary to be part of the Plan. EPD will provide written notice to the permittee of the information necessary and the time line for submittal.

- However, where manual and automatic sampling are impossible (as defined in this permit), or are beyond the permittee's control, the permittee shall take samples as soon as possible, but in no case more than twelve (12) hours after the beginning of the stormwater discharge.
- Sampling by the permittee shall occur for the following qualifying events:

- For each area of the site that discharges to a receiving water or from an outfall, the first rain event that reaches or exceeds 0.5 inch with a stormwater discharge that occurs during normal business hours as defined in this permit after all clearing and grubbing operations have been completed, but prior to completion of mass grading operations, in the drainage area of the location selected as the sampling location;
- In addition to (a) above, for each area of the site that discharges to a receiving water or from an outfall, the first rain event that reaches or exceeds 0.5 inch with a stormwater discharge that occurs during normal business hours as defined in this permit either 90 days after the first sampling event or after all mass grading operations have been completed, but prior to submittal of a NOT, in the drainage area of the location selected as the sampling location, whichever comes first;
- At the time of sampling performed pursuant to (a) and (b) above, if BMPs in any area of the site that discharges to a receiving water or from an outfall are not properly designed, installed and maintained, corrective action shall be defined and implemented within two (2) business days, and turbidity samples shall be taken from discharges from that area of the site for each subsequent rain event that reaches or exceeds 0.5 inch during normal business hours until the selected turbidity standard is attained, or until post-storm event inspections determine that BMPs are properly designed, installed and maintained;
- Where sampling pursuant to (a), (b) or (c) above is required but not possible (or not required because there was no discharge), the permittee, in accordance with Part IV.D.4.a.(6), must include a written justification in the inspection report of why sampling was not performed. Providing this justification does not relieve the permittee of any subsequent sampling obligations under (a), (b) or (c) above; and
- Existing construction activities, i.e., those that are occurring on or before the effective date of this permit, that have met the sampling required by (a) above shall sample in accordance with (b). Those existing construction activities that have met the sampling required by (b) above shall not be required to conduct additional sampling other than as required by (c) above.

- Non-stormwater discharges.** Except for flows from fire fighting activities, sources of non-stormwater listed in Part III.A.2. of this permit that are combined with stormwater discharges associated with construction activity must be identified in the Plan. The Plan shall identify and ensure the implementation of appropriate pollution prevention measures for the non-stormwater component(s) of the discharge.

E. Reporting.

- The applicable permittees are required to submit the sampling results to the EPD at the address shown in Part II.C. by the fifteenth day of the month following the reporting period. Reporting periods are months during which samples are taken in accordance with this permit. Sampling results shall be in a clearly legible format. Upon written notification, EPD may require the applicable permittee to submit the sampling results on a more frequent basis. Sampling and analysis of any stormwater discharge(s) or the receiving water(s) beyond the minimum frequency stated in this permit must be reported in a similar manner to the EPD. The sampling reports must be signed in accordance with Part V.G.2. Sampling reports must be submitted to EPD using the electronic submittal service provided by EPD. Sampling reports must be submitted to EPD until such time as a NOT is submitted in accordance with Part VI.

- All written correspondence required by this permit shall be submitted by return receipt certified mail (or similar service) to the appropriate District Office of the EPD according to the schedule in Appendix A of this permit. The permittee shall retain a copy of the proof of submittal at the construction site or the proof of submittal shall be readily available at a designated location from commencement of construction until such time as a NOT is submitted in accordance with Part VI.

- The rainfall amount, date, exact place and time of sampling or measurements;
- The name(s) of the certified personnel who performed the sampling and measurements;
- The date(s) analyses were performed;
- The time(s) analyses were initiated;
- The name(s) of the certified personnel who performed the analyses;
- References and written procedures, when available, for the analytical techniques or methods used;
- The results of such analyses, including the bench sheets, instrument readouts, computer disks or tapes, etc., used to determine these results;
- Results which exceed 1000 NTU shall be reported as "exceeds 1000 NTU"; and
- Certification statement that sampling was conducted as per the Plan.

"I certify under penalty of law that this Plan was prepared after a site visit to the locations described herein by myself or my authorized agent, under my supervision."

"I certify that the permittee's Erosion, Sedimentation and Pollution Control Plan provides for an appropriate and comprehensive system of best management practices required by the Georgia Water Quality Control Act and the document "Manual for Erosion and Sediment Control in Georgia" (Manual) published by the Georgia Soil and Water Conservation Commission as of January 1 of the year in which the land-disturbing activity was permitted, provides for the sampling of the receiving water(s) or the sampling of the stormwater outfalls and that the designed system of best management practices and sampling methods is expected to meet the requirements contained in the General NPDES Permit No. GAR100001."

CERTIFIED BY : Mark A. Boswell
Level II Certification No. 2104

STREAM BUFFER ENCROACHMENT NOTES :

- NEW STRUCTURES ON THIS PROJECT DO NOT ENCRoACH IN THE 25 OR 50 FOOT STREAM BUFFER.
- NON-EXEMPT ACTIVITIES SHALL NOT BE CONDUCTED WITHIN THE 25 OR 50 FOOT UNDISTURBED STREAM BUFFERS AS MEASURED FROM THE POINT OF WRECKED VEGETATION OR WITHIN 25 FEET OF THE COASTAL MARSHLAND BUFFER AS MEASURED FROM THE JURISDICTIONAL DETERMINATION LINE WITHOUT FIRST ACQUIRING THE NECESSARY VARIANCES AND PERMITS.

LEVEL II
CERTIFICATION
NO. 2104
ISSUED 11-5-05
EXPIRES 11-15-26

REVISIONS					

BOSWELL DESIGN SERVICES, INC.

OFFICE: 4700 EAST HIGHWAY 80
Unit N, Suite 1
MAILING: 103 NASSAU DRIVE
SAVANNAH, GEORGIA 31410
912-897-6932
LAHBOS@Bellsouth.net



CHECKED	DATE	SCALE	OR SHOWN
DRAWN	DATE	JOB NO.	
MSD	OCT 6, 2025		
DESIGNED			


MOSAIC GALLERIA
125 HIGH AVENUE
POOLER, GEORGIA 31322
MOSAIC FIVE, LLC
BEAUFORT, SOUTH CAROLINA

NOTES AND DETAILS

CONTACT A MINIMUM OF 72 HOURS
PRIOR TO DIGGING



UTILITIES PROTECTION CENTER
1-800-282-7411



DRAWING NUMBER

C-21

Dust Control on Disturbed Areas

Du



DEFINITION
Controlling surface and air movement of dust on construction sites, roads, and demolition sites.

PURPOSE
• To prevent surface and air movement of dust from exposed soil surfaces.

• To reduce the presence of airborne substances that may be harmful or injurious to human health, welfare, or safety, or to animals or plant life.

CONDITIONS
This practice is applicable to areas subject to surface and air movement of dust where on and off-site damage may occur without treatment.

METHOD AND MATERIALS

A. Temporary Methods

Mulches. See standard Ds1 - Disturbed Area Stabilization (With Mulching Only). Synthetic resins may be used instead of asphalt to bind mulch material. Refer to specification Tac - Tackifiers. Resins should be used according to manufacturer's recommendations.

Vegetative Cover. See specification Ds2 - Disturbed Area Stabilization (With Temporary Seeding).

Spray-on Adhesives. These are used on mineral soils (not effective on muck soils). Keep traffic off these areas. Refer to specification Tac - Tackifiers.

Tillage. This practice is designed to roughen and bring clods to the surface. It is an emergency

measure that should be used before wind erosion starts. Begin plowing on windward side of site. Chisel-type plows spaced about 12 inches apart, spring-toothed harrows, and similar plows are examples of equipment that may produce the desired effect.

Irrigation. This is generally done as an emergency treatment. Site is sprinkled with water until the surface is wet. Repeat as needed.

Barriers. Solid board fences, snowfences, burlap fences, crate walls, bales of hay and similar material can be used to control air currents and soil blowing. Barriers placed at right angles to prevailing currents at intervals of about 15 times their height are effective in controlling wind erosion.

Calcium Chloride. Apply at rate that will keep surface moist. May need retreatment.

B. Permanent Methods

Permanent Vegetation. See specification Ds3 - Disturbed Area Stabilization (With Permanent Vegetation). Existing trees and large shrubs may afford valuable protection if left in place.

Topsoiling. This entails covering the surface with less erosive soil material. See specification Tp - Topsoiling.

Stone. Cover surface with crushed stone or coarse gravel. See specification Cr-Construction Road Stabilization.

Check Dam Cd



DEFINITION
A temporary grade control structure, or dam constructed across a swale, drainage ditch, or area of concentrated flow.

PURPOSE
To minimize the erosion rate by reducing the velocity of the storm water in areas of concentrated flow.

CONDITIONS
This practice is applicable for use in small open channels and is not to be used in a live stream. Specific applications include:

1. Temporary or permanent swales or ditches in need of protection during establishment of grass linings.
2. Temporary or permanent swales or ditches that, due to their short length of service or other reasons, cannot receive a permanent non-erodible lining for an extended period of time.
3. Other locations where small localized erosion and resulting sedimentation problems exist.

DESIGN CRITERIA
Check dams should be designed using 2.0 cfs. For any flows exceeding 2.0 cfs, check dams may be used in conjunction with other BMPs in the channel. Dam height should be 24 inches maximum measured to the center of the check dam.

Drainage Area
For stone check dams, the drainage area shall not exceed two acres. For straw-bale check dams and compost filter socks, the drainage area shall not exceed one acre.

Side Slopes
Side slopes shall be 2:1 or flatter.

Spacing
Two or more check dams in a series shall be used for drainage areas greater than one (1) acre. Maximum spacing between dams should be such that the toe of the upstream dam is at the same elevation as the top of the downstream dam. (See Figure 6-12.1.)

Geotextiles
A geotextile should be used as a separator between the graded stone and the soil base and abutments. The geotextile will prevent the migration of soil particles from the subgrade into the graded stone. The geotextile shall be selected/specified in accordance with AASHTO M288-06 Section 7.3, Separation Requirements, Table 3. Geotextiles shall be "set" into the subgrade soils. The geotextile shall be placed immediately adjacent to the subgrade without any voids and extend five feet beyond the downstream toe of the dam to prevent scour.

CONSTRUCTION SPECIFICATIONS

Stone Check Dams Cd-S

Stone check dams should be constructed of graded size 2-10 inch stone. Mechanical or hand placement shall be required to insure complete coverage of the entire width of the ditch or swale and that the center of the dam is lower than the edges. The center of the check dam must be at least 9 inches lower than the outer edges. (See Figure 6-12.2.)

Straw-bale Check Dams Cd-Hb

Staked and embedded straw-bales may be used as temporary check dams in concentrated flow areas while vegetation is becoming established. They shall not be used where the drainage area exceeds one acre. Straw-bales should be installed per Figure 6-12.3.

Installation

Bales should be bound with wire or nylon string. Twine bound bales are less durable. The bales should be placed in rows with bales ends tightly abutting the adjacent bales.

Downstream Row (Refer to Figure 6-12.3)
Dig a trench across the small channel, wide enough and deep enough so that the top of the row of bales placed on their long, wide side is level with the ground. The tops of bales across the center of the channel should be at level and set at the same elevation. Place the bales in position and stake them according to the instructions below.

Upstream Row
Dig another trench across the small channel, upstream and immediately adjacent to the first row of bales. The trench should be wide enough to accommodate a row of bales set vertically on their long edge. The trench should be deep enough so that at least 6 inches of each bale is below ground starting with the bale in the channel bottom. The trench should be as level as possible so that the tops of the bales across the center of the channel are level and water can flow evenly across them. Continue this trench up the side slopes of the small channel to a point where the unbursed bottom line of the highest bale (Point "C", Figure 6-12.3) is higher than the top of the bales that are in the center of the channel (Point "D", Figure 6-12.3).

Anchorage

Drive standard 2 x 2 stakes or #4 rebar through the bales and into the ground 1 1/2 to 2 feet for anchorage. The first stake in each bale should be driven toward a previously laid bale to force the bales together (See Figure 6-12.3).

Reference: Colorado NRCS Straw Bale Check Dam

Compost Filter Sock Cd-Fs

The filter sock should be staked in the center. If the compost filter sock is to be left as a permanent filter or part of the natural landscape, it may be seeded at time of installation for establishment of permanent vegetation.

Compost filter media used for compost filter sock filter material shall be weed free and derived from

a well-decomposed source of organic matter.

The compost shall be produced using an aerobic composting process meeting CFR 503 regulations including time and temperature data.

The compost shall be free of any refuse, contaminants or other materials toxic to plant growth. Non-composted products will not be accepted.

Test methods for the items below should follow US Composting Council Test Methods for the Examination of Composting and Compost guidelines for laboratory procedures.

A. pH = 5.0-8.0 in accordance with TMECC 04.11-A, "Electrometric pH Determinations for Compost".

B. Particle size - 90% passing a 2-inch (50 mm) sieve and a maximum of 40% passing a 3/8-inch (~9.5 mm) sieve. In accordance with TMECC 02.02-B, "Sample Sieving for Aggregate Size Classification." Note - In the field, product commonly is between 1/2 and 2 inches (12.5 and 50 mm) particle size).

C. Moisture content of less than 60% in accordance with standardized test methods for moisture determination.

D. Material shall be relatively free (<1% by dry weight) of inert or foreign manmade materials.

E. Sock containment system for compost filter media shall be a photodegradable or biodegradable knitted mesh material and should have 1/8 to 3/8 inch (3.2 to 9.5 mm) openings.

MAINTENANCE
Periodic inspection and required maintenance must be provided. Sediment shall be removed when it reaches a depth of one-half the original dam height or before. If the area is to be moved, check dams shall be removed once final stabilization has occurred. Otherwise check dams may remain in place permanently. After removal, the area beneath the dam shall be seeded and mulched immediately.

State of Georgia
Department of Natural Resources
Environmental Protection Division

Page 35 of 46
Permit No. GAR100001

(b). The downstream sample for each receiving water(s) must be taken downstream of the confluence of the last stormwater discharge from the permitted activity (i.e., the discharge farthest downstream at the site) but upstream of any other stormwater discharge not associated with the permitted activity. Where appropriate, several downstream samples from across the receiving water(s) may need to be taken and the arithmetic average of the turbidity of these samples used for the downstream turbidity value.

(c). Ideally the samples should be taken from the horizontal and vertical center of the receiving water(s) or the stormwater outfall channel(s).

(d). Care should be taken to avoid stirring the bottom sediments in the receiving water(s) or in the outfall stormwater channel.

(e). The sampling container should be held so that the opening faces upstream.

(f). The samples should be kept free from floating debris.

(g). Permitteds do not have to sample sheet flow that flows onto undisturbed natural areas or areas stabilized by the project. For purposes of this section, stabilized shall mean, for unpaired areas and areas not covered by permanent structures and areas located outside the waste disposal limits of a landfill cell that has been certified by EPA for waste disposal, 100% of the soil surface is uniformly covered in permanent vegetation with a density of 70% or greater, or landscaped according to the Plan (uniformly covered with landscaping materials in planned landscaped areas), or equivalent permanent stabilization measures as defined in the Manual (including a crop of annual vegetation and a seeding of target crop perennials appropriate for the region).


(h). All sampling pursuant to this permit must be done in such a way (including generally accepted sampling methods, locations, timing, and frequency) as to accurately reflect whether stormwater runoff from the construction site is in compliance with the standard set forth in Parts III.D.3. or III.D.4., whichever is applicable.

d. Sampling Frequency:


(1). The primary permittee must sample in accordance with the Plan at least once for each rainfall event described below. For a qualifying event, the permittee shall sample at the beginning of any stormwater discharge to a monitored receiving water and/or from a monitored outfall location within in forty-five (45) minutes or as soon as possible.

STONE CHECK DAM

CROSS SECTION



PROFILE VIEW



- NOTES:**
1. CHECK DAMS ARE TO BE USED ONLY IN SMALL OPEN CHANNELS (THEY ARE NOT TO BE USED IN LIVE STREAMS).
 2. THE DRAINAGE AREA FOR STONE CHECK DAMS SHALL NOT EXCEED TWO ACRES.
 3. THE CENTER OF THE CHECK DAM MUST BE AT LEAST 9 INCHES LOWER THAN THE OUTER EDGES.
 4. THE DAM HEIGHT SHOULD BE A MAXIMUM OF 2 FEET FROM CENTER TO RIM EDGE. THE SIDE SLOPES OF THE CHECK DAM SHALL NOT EXCEED A 2:1 SLOPE.
 5. GEOTEXTILE SHALL BE USED TO PREVENT THE MIGRATION OF SUBGRADE SOIL PARTICLES INTO THE STONES (REFER TO AASHTO M288-96, SECTION 7.3, TABLE 3).

Figure 6-12.2

6-42

GBWCC 2016 Edition

Temporary Sediment Trap Sd4



DEFINITION
A small temporary pond that drains a disturbed area so that sediment can settle out. The principle feature distinguishing a temporary sediment trap from a temporary sediment basin is the lack of a pipe or riser.

PURPOSE
To collect and store sediment from uphill sites cleared or graded during construction, intended for use on small tributary areas with no unusual drainage features. Effective against coarse sediment, but not against silt or clay particles that remain suspended.

CONDITIONS
Temporary sediment traps are constructed early in the construction process at locations that will require minimal clearing and grading. Natural draws or swells are favorable locations to build the traps. They should be easily accessible for frequent maintenance and inspections. Temporary sediment traps shall never be placed in live streams.

DESIGN CRITERIA
Design and construction shall comply with laws, ordinances, rules and regulations on the local, state and federal level.

The total drainage area of a temporary sediment trap is up to 5 acres, depending on type of construction.

The height of a temporary sediment trap embankment shall not exceed 5.5 feet as measured from the downstream toe of slope to the top of the berm. Top width of an embankment shall be

at least as wide as the height of the sediment trap embankment, with a minimum width of 3 feet.

Maximum pond depth of a sediment trap is 4 feet as measured from the bottom of the trap to the invert of the emergency spillway. Slopes shall not exceed 2:1 (H:V) for excavated areas and for compacted embankments. Side slopes should be (3:1) or flatter allowing people and equipment to safely negotiate slopes or to enter the sediment trap.

The length to width ratio must be greater than (2:1) (L:W) for the principal flowpaths in order to maintain residence time of stormwater within the sediment trap. Baffles may be required to prevent short-circuiting of the flow.

A typical baffle design uses 4"x6" sheets of exterior grade plywood 1/2 inch thick, mounted on 4"x4" hardwood posts.

Volume
Minimum volume of a temporary sediment trap shall be 67 cubic yards per acre for the total drainage area. The volume shall be measured at an elevation equivalent to the spillway invert.

Volume of a temporary sediment trap in heavily disturbed areas should be 134 cubic yards per acre for the total drainage area. This includes an upper area with a minimum of 67 cubic yards per acre drained, which is dewatered using one of the outlet design methods provided, and a lower wet zone for sediment storage and settling.

The volume should be calculated from existing and proposed contours, or by measured cross sections. An approximate method for calculating the volume of traps using a natural draw is:

$V = 0.4 \times A \times D$
V = Sediment storage volume (below invert of emergency spillway)
A = Surface area (at level of emergency spillway)
D = Maximum depth (from emergency spillway invert)

The dewatered volume for a temporary sediment trap is 1/3 of the total storage volume. Channel volume shall be calculated and marked with a stake at the outlet of the trap.

CONSTRUCTION SPECIFICATIONS

The basic design guidelines are applicable to the type of temporary sediment trap constructed. The main differences are with regards to the type of outlet structures. The following types of construction are acceptable under the designated conditions:

Overflow (Sd4-A)
An overflow temporary sediment trap is typically used in small areas less than 1 acre, typically with gentle slopes (1 or 2 percent) and without the need for grading operations. The maximum life span of an overflow trap is 6 months. If water enters the trap with low velocities, the small amount of water will be slowly displaced and leave the other end of the sediment trap. Staked straw bale barriers or grass filter strips are used to "polish" the overflow water before it enters the sediment trap. See Figure 6-30.1.


Combination Straw Bale and Silt Fence Outlet (Sd4-B)
The combination straw bale and silt fence outlet trap is designed to collect sediment from the total drainage area. The volume shall be measured at an elevation equivalent to the spillway invert. The material to resist 1 foot or more of ponded water. The combination straw bale and silt fence outlet is limited to 1 acre total drainage area and has a life span of less than 1 year. This type of outlet requires frequent maintenance and inspections to ensure the released stormwater is free of sediment. See Figure 6-30.2.

Rock Outlet (Sd4-C)
The rock outlet relies on filtering through layers of aggregate, rock or riprap material to dewater the sediment trap. It is the sturdiest of the sediment trap designs and generally requires less maintenance. It can be used for drainage area up to 5 acres and has a life span of 1 year. See Figure 6-30.3.

Emergency Spillway
The emergency overflow outlet of a temporary sediment trap must be stabilized with rock, geotextile, vegetation, or another suitable material that is resistant to erosion. It must be installed to safely convey stormwater runoff for the 10-year storm event.

REFERENCE:
City of Knoxville BMP Manual Best Management Practices, Knoxville, TN, May 2003

TEMPORARY SEDIMENT TRAP ROCK OUTLET



SEE APPENDIX C FOR STONE CHECK DAM MINIMUM DISTANCE 1.5' TO SPILLWAY INVERT.

MINIMUM TOP WIDTH = EMBANKMENT HEIGHT (3 FOOT MINIMUM) MAX. SLOPE 2:1

MINIMUM TOP WIDTH = 3' MIN. MAX. SLOPE 2:1

RECOMMENDED MINIMUM RATIO OF LENGTH-TO-WIDTH (L:W) IS 2:1

EXCAVATED MATERIAL WILL INCREASE STORAGE VOLUME AND PROVIDE FILL INTO NATURAL GROUND

MINIMUM TOP WIDTH = 3' MIN. MAX. SLOPE 2:1

REPRAP GEOTEXTILE FABRIC (KEYED INTO GROUND)

MINIMUM TOP WIDTH = 3' MIN. MAX. SLOPE 2:1

REPRAP GEOTEXTILE FABRIC (KEYED INTO GROUND)

MINIMUM TOP WIDTH = 3' MIN. MAX. SLOPE 2:1

REPRAP GEOTEXTILE FABRIC (KEYED INTO GROUND)

MINIMUM TOP WIDTH = 3' MIN. MAX. SLOPE 2:1

REPRAP GEOTEXTILE FABRIC (KEYED INTO GROUND)

MINIMUM TOP WIDTH = 3' MIN. MAX. SLOPE 2:1

REPRAP GEOTEXTILE FABRIC (KEYED INTO GROUND)

MINIMUM TOP WIDTH = 3' MIN. MAX. SLOPE 2:1

REPRAP GEOTEXTILE FABRIC (KEYED INTO GROUND)

MINIMUM TOP WIDTH = 3' MIN. MAX. SLOPE 2:1

REPRAP GEOTEXTILE FABRIC (KEYED INTO GROUND)

MINIMUM TOP WIDTH = 3' MIN. MAX. SLOPE 2:1

REPRAP GEOTEXTILE FABRIC (KEYED INTO GROUND)

MINIMUM TOP WIDTH = 3' MIN. MAX. SLOPE 2:1

REPRAP GEOTEXTILE FABRIC (KEYED INTO GROUND)

MINIMUM TOP WIDTH = 3' MIN. MAX. SLOPE 2:1

REPRAP GEOTEXTILE FABRIC (KEYED INTO GROUND)

MINIMUM TOP WIDTH = 3' MIN. MAX. SLOPE 2:1

STREAM BUFFER ENCROACHMENT NOTES :

1. NEW STRUCTURES ON THIS PROJECT DO NOT ENCR OACH IN THE 25 OR 50 FOOT STREAM BUFFER.
2. NON-EXEMPT ACTIVITIES SHALL NOT BE CONDUCTED WITHIN THE 25 OR 50 FOOT UNDISTURBED STREAM BUFFERS AS MEASURED FROM THE POINT OF WRESTED VEGETATION OR WITHIN 25 FEET OF THE COASTAL MARSHLAND BUFFER AS MEASURED FROM THE JURISDICTIONAL DETERMINATION LINE WITHOUT FIRST ACQUIRING THE NECESSARY VARIANCES AND PERMITS.

WETLAND AREA NOTE :

1. CONTRACTOR IS TO VERIFY WETLAND PERMITS WITH OWNER PRIOR ANY LAND DISTURBANCE IN WETLAND OR WETLAND BUFFER AREAS.

LEVEL II
CERTIFICATION
NO. 2104
ISSUED 11-5-05
EXPIRES 11-15-26

SPECIAL CONSTRUCTION NOTE:

IF THE CONTRACTOR KNOWS OR CAN REASONABLY BE EXPECTED TO HAVE KNOWN OF AN ERROR, DISCREPANCY OR CONFLICT IN THE PLANS, SPECIFICATIONS OR CONSTRUCTION STAKING AND FAILS TO REPORT THE PROBLEM PRIOR TO CONSTRUCTION, HE SHALL NOT BE ENTITLED TO COMPENSATION FOR ANY WORK OR EXPENSE INCURRED BY HIM FOR WORK REQUIRED TO BE RE-CONSTRUCTED BECAUSE OF SAID ERROR, DISCREPANCY OR CONFLICT.

CHECKED
DESIGNED
DRAWN
DATE
OCT 6, 2025
JOB NO.
SCALE
as shown

MOSAIC GALLERIA
125 HIGH AVENUE
POOLER, GEORGIA 31322
MOSAIC FIVE, LLC
BEAUFORT, SOUTH CAROLINA
NOTES AND DETAILS

CONTACT A MINIMUM OF 72 HOURS
PRIOR TO DIGGING
UTILITIES PROTECTION CENTER
1-800-282-7411

GEORGIA
REGISTERED
No. 28372
PROFESSIONAL
I.O.-E.-25
ENGINEER
MARK A. BOSWELL

DRAWING NUMBER

C-22

22 OF 28 SHEETS

BOSWELL DESIGN SERVICES, INC.
OFFICE: 4700 EAST HIGHWAY 80
Unit N, Suite 1
MAILING: 103 NASSAU DRIVE
SAVANNAH, GEORGIA 31410
912 - 897 - 6932
LAHBOS@belsouth.net

Disturbed Area Stabilization (With Permanent Vegetation)



DEFINITION
The planting of perennial vegetation such as trees, shrubs, vines, grasses, or legumes on exposed areas for final permanent stabilization. Permanent stabilization shall be used to achieve final stabilization.

PURPOSE
-To protect the soil surface from erosion
-To reduce damage from sediment and runoff to down-stream areas
-To improve wildlife habitat and visual resources
-To improve aesthetics

REQUIREMENT FOR REGULATORY COMPLIANCE

This practice shall be applied immediately to rough graded areas that will be undisturbed for longer than six months. This practice or sodding shall be applied immediately to all areas of final grade. Final Stabilization means that all soil disturbing activities at the site have been completed, and that for ungraded areas and areas not covered by permanent structures and areas located outside the waste disposal limits of a landfill cell that has been certified by the GA EPD for waste disposal, 100% of the soil surface is uniformly covered in permanent vegetation with a density of 70% or greater, or landscaped according to the Plan (uniformly covered with landscaping materials in planned landscaped areas), or equivalent permanent stabilization measures.

Permanent vegetation shall consist of: planted trees, shrubs, perennial vines; or a crop of perennial vegetation appropriate for the region, such that within the growing season a 70% coverage by perennial vegetation shall be achieved. Final stabilization applies to such phases of construction. For linear construction projects on land, used for agricultural or silvicultural purposes, final stabilization may be accomplished by stabilizing the disturbed land for its agricultural or silvicultural use. Until this standard is satisfied and permanent control measures and facilities are operational, interim stabilization measures and temporary erosion and sedimentation control measures shall not be removed.

COMPLIANCE
Permanent perennial vegetation is used to provide a protective cover for exposed areas including cuts, fills, dikes, and other denuded areas.

PLANNING CONSIDERATIONS

1. Use conventional planting methods where possible.
2. When mixed plantings are done during marginal planting periods, companion crops shall be used.
3. No till planting is effective when planting is done following a summer or winter annual cover crop. *Senecio lespedeza* planted well into stands of ryegrass is an excellent procedure.
4. Block sod provides immediate cover. It is especially effective in controlling erosion adjacent to concrete flumes and other structures. Refer to Specification D-4-Disturbed Area Stabilization (With Sodding).
5. Irrigation should be used when the soil is dry or when summer plantings are done.
6. Low maintenance plants, as well as natives, should be used to ensure long-lasting erosion control.
7. Mowing should not be performed during the quail nesting season (May to September).
8. Wildlife plantings should be included in critical area plantings.

Wildlife Plantings
Commercially available plants beneficial to wildlife species include the following:
Most Bearing Trees
Beech, Black Cherry, Blackgum, Chestnut, Chickadee, Hackberry, Hickory, Honey Locust, Native Oak, Persimmon, Sawtooth Oak, Sweetgum.
All trees that produce nuts or fruits are favored by many game species. Hickory provides nuts used mainly by squirrels and bear.

Shrubs and Small Trees
Bayberry, Bicolor Lespedeza, Crabapple, Dogwood, Huckleberry or Native Blueberry, Mountain Laurel, Native Holly, Red Cedar, Red Mulberry, Sumac, Wax Myrtle, Wild Plum and Blackberry.

Plant in patches without tall trees to develop stable shrub communities. All produce fruits used by many kinds of wildlife, except for *Lespedeza* that produces seeds used by quail and songbirds.
Grasses, Legumes, Vines and Temporary Cover
Bahiagrass, Bermudagrass, Grass-Legume mixtures, Partridge Pea, Annual Lespedeza, Orchardgrass (for mountains), Browntop Millet (for temporary cover), and Native grasses.
Provides herbaceous cover in clearings for a game bird brood-rearing habitat. Appropriate legumes such as vetches, clovers, and lespedesas may be mixed with grass, but they may die out after a few years.

Block sod provides immediate cover. It is especially effective in controlling erosion adjacent to concrete flumes and other structures. Refer to Specification D-4-Disturbed Area Stabilization (With Sodding).

CONSTRUCTION SPECIFICATIONS

Grading and Shaping
Grading and shaping may not be required where hydraulic seeding and fertilizing equipment is to be used. Vertical banks shall be sloped to enable plant establishment.
When conventional seeding and fertilizing are to be done, grade and shape where feasible and practical, so that equipment can be used safely and efficiently during seedbed preparation, seeding, mulching and maintenance of the vegetation.
Concentrations of water that will cause excessive

soil erosion shall be diverted to a safe outlet. Diversion and other treatment practices shall conform with the appropriate standards and specifications.

Line and Fertilizer Rates and Analysis
Agricultural lime is required at the rate of one to two tons per acre unless soil tests indicate otherwise. Graded areas require lime application. If lime is applied within six months of planting, permanent perennial vegetation, additional lime is not required. Agricultural lime shall be within the specifications of the Georgia Department of Agriculture.
Lime spread by conventional equipment shall be "ground limestone" (ground limestone is calcitic or dolomitic limestone ground to 10-mesh sieve, not less than 50 percent will pass through a 50-mesh sieve and not less than 25 percent will pass through a 100-mesh sieve).

Fast-acting lime spread by hydraulic seeding equipment shall be "finely ground limestone" spanning from the 160 micron size to the 5-micron size. Finely ground limestone is calcitic or dolomitic limestone ground so that 35 percent of the material will pass through a 100-mesh sieve.

It is desirable to use dolomitic limestone in the Sand Hills, Southern Coastal Plain and Atlantic Coast Flatwoods MLRAs. (See Figure 6-4-1).

Agricultural lime is generally not required where only trees are planted.

Initial fertilization, nitrogen, topdressing, and maintenance fertilizer requirements for each species or combination of species are listed in Table 6-5-1.

Line and Fertilizer Application

When hydraulic seeding equipment is used, the initial fertilizer shall be mixed with seed, inoculant (if needed), and wood cellulose or wood pulp fiber mulch and applied in a slurry. The inoculant, if needed, shall be mixed with the seed prior to being placed into the hydraulic seeder. The slurry mixture will be applied during seedbed preparation. The mixture will be spread uniformly over the area within one hour after being placed in the

hydroseeder.

Finely ground limestone can be applied in the mulch slurry or in combination with the top-dressing. When conventional planting is to be done, lime and fertilizer shall be applied uniformly in one of the following ways:

1. Apply before land preparation so that it will be mixed with the soil during seedbed preparation.
2. Mix with the soil used to fill the holes, distribute in furrows.
3. Broadcast after steep surfaces are scarified, pitfaced or trenched.
4. A fertilizer pellet shall be placed at root depth in the closing hole beside each pine tree seedling.

Plant Selection

Refer to Tables 6-4-1, 6-5-2, 6-5-3 and 6-5-4 for approved species. Species not listed shall be approved by the State Resource Conservationist of the Natural Resources Conservation Service before they are used.

Plants shall be selected on the basis of species characteristics, site and soil conditions, planned use and maintenance of the area: time of year of planting, method of planting, and the needs and desires of the land user.

Some perennial species are easily established and can be mixed with grass, but they may die out after a few years.

Other Perennials, such as Bahia Grass and Sericea lespedeza, are slow to become established and should be planted with another perennial species. The additional species will provide quick cover and ample soil protection until the target perennial species become established. For example, Common seedling combinations are 1) Weeping Lovegrass with Sericea lespedeza (scarified) and 2) Tall Fescue with Sericea lespedeza (unscarified).

Plant selection may also include annual companion crops. Annual companion crops should be used only when the perennial species are not planted during their optimum planting period. A common

mixture is Brown Top Millet with Common Bermuda in mid-summer. Care should be taken in selecting companion crop species and seeding rates because annual crops will compete with perennial species for water, nutrients, and growing space. A high seeding rate of the companion crop may prevent the establishment of perennial species.

Regrasses shall not be used in any seeding mixtures containing perennial species due to its ability to out-compete desired species chosen for permanent perennial cover.

Seed Quality

The term "pure live seed" is used to express the quality of seed and is not shown on the label. Pure live seed, PLS, is expressed as a percent: age of the seeds that are pure and will germinate. Information on pure live seed may lodge and germinate. Hydraulic seeding may also be used.

PLS = % germination x % purity

EXAMPLE:
Common Bermuda seed
70% germination, 80% purity
PLS = 70% germination x 80% purity
PLS = 56%

The percent of PLS helps you determine the amount of seed you need. If the seeding rate is 10 pounds PLS and the bulk seed is 56 % PLS, the bulk seeding rate is:

10 lbs. PLS/acre = 17.9 lbs/acre
56% PLS

You would need to plant 17.9 lbs/acre to provide 10 pounds of pure live seed.

Seedbed Preparation

Seedbed preparation may not be required where hydraulic seeding and fertilizing equipment is to be used (but is strongly recommended for any seeding process, when possible). When conventional seeding is to be used, seedbed preparation will be done as follows:

Broadcast plantings

1. Tillage, at a minimum, shall adequately

loosen the soil to a depth of 4 to 6 inches; alleviate compaction; incorporate lime and fertilizer; smooth and firm the soil; allow for the proper placement of seed, sprigs, or plants; and allow for the anchoring of straw or hay mulch if a disk is to be used.

2. Tillage may be done with any suitable equipment.
3. Tillage should be done on the contour where feasible.
4. On slopes too steep for the safe operation of tillage equipment, the soil surface shall be pitfaced or trenched across the slope with appropriate hand tools to provide two places age of 8 inches apart in which seed may lodge and germinate. Hydraulic seeding may also be used.

Individual Plants

1. Where individual plants are to be set, the soil shall be prepared by excavating holes, opening furrows, or double planting.
2. For nursery stock plants, holes shall be large enough to accommodate roots without crowding.
3. Where pine seedlings are to be planted, subsoil under the row 36 inches deep on the contour four to six months prior to planting. Subsoiling should be done when the soil is dry, preferably in August or September.

Inoculants

All legume seed shall be inoculated with appropriate nitrogen-fixing bacteria. The inoculant shall be a pure culture prepared specifically for the seed species and used within the dates on the container.

A mixing medium recommended by the manufacturer shall be used to bond the inoculant to the seed. For conventional seeding, use twice the amount of inoculant recommended by the manufacturer. For hydraulic seeding, four times the amount of inoculant recommended by the manufacturer shall be used.

All inoculated seed shall be protected from the sun and high temperatures and shall be planted

the same day inoculated. No inoculated seed shall remain in the hydroseeder longer than one hour.

Planting Hydraulic Seeding
Mix the seed (inoculated if needed), fertilizer, and wood cellulose or wood pulp fiber mulch with water and apply in a slurry uniformly over the area to be treated. Apply within one hour after the mixture is made.

Conventional Seeding
Seeding will be done on a freshly prepared and firmed seedbed. For broadcast planting, use a culti-packer-seeder, drill, rotary seeder, other mechanical seeder, or hand seeding to distribute the seed uniformly over the area to be treated. Cover the seed lightly with 1/8 to 1/4 inch of soil for small seed and 1/2 to 1 inch for large seed, when using a cultipacker or other suitable equipment.

No-Till Seeding
No-till seeding is permissible into annual cover crops when planting is done following maturity of the cover crop or if the temporary cover stand is sparse enough to allow adequate growth of the permanent (perennial) species. No-till seeding shall be done with appropriate no-till seeding equipment. The seed must be uniformly distributed and planted at the proper depth.

Individual Plants
Shrubs, vines and sprigs may be planted with appropriate planters or hand tools. Pine trees shall be planted manually in the subsoil furrow. Each plant shall be set in a manner that will avoid crowding the roots.

Nursery stock plants shall be planted at the same depth or slightly deeper than they grew at the nursery. The tips of vines and sprigs must be at or slightly above the ground surface.

When individual holes are dug, fertilizer shall be placed in the bottom of the hole, two inches of soil shall be added and the plant shall be set in the hole.

Mulching
Mulch is required for all permanent vegetation applications. Mulch applied to seeded areas shall achieve 75% to 100% soil cover. When selecting a mulch, design professionals should consider the mulch's functional longevity, vegeta-

tion establishment enhancement, and erosion control effectiveness. Select the mulching material from the following and apply as indicated:

1. Dry straw or dry hay of good quality and free of weed seeds can be used. Dry straw shall be applied at the rate of 2 tons per acre. Dry hay shall be applied at a rate of 2 1/2 tons per acre.
2. Wood cellulose mulch or wood pulp fiber shall be used with hydraulic seeding. It shall be applied at the rate of 500 pounds per acre. Dry straw or dry hay shall be applied (at the rate indicated above) after hydraulic seeding.
3. One thousand pounds of wood cellulose or wood pulp fiber, which includes a tackifier, shall be used with hydraulic seeding on slopes 3:4 or steeper.
4. Sericea lespedeza hay containing mature seed shall be applied at a rate of three tons per acre.
5. Pine straw or pine bark shall be applied at a thickness of 3 inches for bedding purposes. Other suitable materials in sufficient quantity may be used where ornamentals or other ground covers are planted. This is not appropriate for seeded areas.
6. When using temporary erosion control blankets or block sod, mulch is not required.
7. Bituminous treated paving may be applied on planted areas, slopes, in ditches or dry waterways to prevent erosion and to provide a leveling surface. Bituminous treated paving shall be applied within 24 hours after an area has been planted. Application rates and materials must meet Georgia Department of Transportation specifications.

Wood cellulose and wood pulp fibers shall not contain germination or growth inhibiting factors. They shall be evenly dispersed when applied in water. The fibers shall contain a dye to allow visual metering and aid in uniform application during seeding.

Applying Mulch

Straw or hay mulch will be spread uniformly within 24 hours after seeding and/or plant-

ing. The mulch may be spread by blower-type spreading equipment, other spreading equipment or by hand. Mulch shall be applied to cover 75% of the soil surface.

Anchoring Mulch
Anchor straw or hay mulch immediately after application by one of the following methods:

1. Hay and straw mulch shall be pressed into the soil immediately after the mulch is spread. A special "pucker disk" or disk harrow with the disks set straight may be used. The disks may be smooth or serrated and should be 20 inches or more in diameter and 8 to 12 inches apart. The edges of the disks shall be dull enough to press the mulch into the ground without cutting it, leaving much of it in an erect position. Mulch that is not plowed into the soil.
2. Synthetic tackifiers, binders or hydraulic mulch specifically designed to tack straw, shall be applied in conjunction with or immediately after the mulch is spread. Synthetic tackifiers shall be mixed and applied according to manufacturer's specifications. All tackifiers, binders or hydraulic mulch specifically designed to tack straw shall be verified not to contain herbicides or other harmful substances. Refer to Tackifiers-Tac.
3. Rye or wheat can be included with Fall and Winter plantings to stabilize the mulch. They shall be applied at a rate of one-quarter to one-half bushel per acre.
4. Plastic mesh or netting with mesh no larger than one inch by one inch may be needed to anchor straw or hay mulch on unstable soils and concentrated flow areas. These materials shall be installed and secured according to manufacturer's specifications.

Bedding Material

Mulch is used as a bedding material to conserve moisture and control weeds in nurseries, ornamental beds, around shrubs, and on bare areas on lawns.

Material
Grass straw
Grass hay
Pine needles
Wood waste

Depth
4" to 6"
4" to 6"
3" to 5"
4" to 6"

Irrigation
Irrigation will be applied at a rate that will not cause runoff.

Topdressing
Topdressing will be applied on all temporary and permanent (perennial) species planted alone or in mixtures with other species. Recommended rates of application are listed in Table 6-5-1.

Second Year and Maintenance Fertilization
Second year fertilizer rates and maintenance fertilizer rates are listed in Table 6-5-1.

Lime Maintenance Application
Apply one ton of agricultural lime every 4 to 6 years or as indicated by soil tests. Soil tests can be conducted to determine more accurate requirements, if desired.

Use and Management

More Sericea lespedeza only after frost to ensure that the seeds are mature. Mow between November and March.

Bermudagrass, Bahiagrass and Tall Fescue may be mowed as desired. Maintain at least 6 inches of top growth under any use and management. Moderate use of top growth is beneficial after establishment.

Exclude traffic until the plants are well established. Because of the quail nesting season, mowing should not take place between May and September.

Wood cellulose and wood pulp fibers shall not contain germination or growth inhibiting factors. They shall be evenly dispersed when applied in water. The fibers shall contain a dye to allow visual metering and aid in uniform application during seeding.

Applying Mulch
Straw or hay mulch will be spread uniformly within 24 hours after seeding and/or plant-

63WCC 2016 Edition

6-35

6-36

63WCC 2016 Edition

63WCC 2016 Edition

6-37

6-38

63WCC 2016 Edition

63WCC 2016 Edition

6-39

63WCC 2016 Edition

6-40

Table 6-5-1. Fertilizer Requirements				
TYPE OF SPECIES	YEAR	ANALYSIS OR EQUIVALENT N-P-K	RATE	N TOP DRESSING RATE
1. Cool season grasses	First	6-12-12	1500 lbs./ac.	50-100 lbs./ac. 1/2
	Second Maintenance	6-12-12 10-10-10	1000 lbs./ac. 400 lbs./ac.	30
2. Cool season grasses and legumes	First	6-12-12	1500 lbs./ac.	—
	Second Maintenance	6-12-12 10-10-10	1000 lbs./ac. 400 lbs./ac.	—
3. Ground covers	First	10-10-10	1300 lbs./ac. 3/	—
	Second Maintenance	10-10-10 10-10-10	1300 lbs./ac. 3/ 1100 lbs./ac.	—
4. Pine seedlings	First	20-10-5	one 2" gran pellet per seedling placed in the closing hole	—
5. Shrub	First	6-12-12	700 lbs./ac.	—
	Maintenance	6-12-12 10-10-10	700 lbs./ac. 4/	—
6. Temporary cover crops seeded alone	First	10-10-10	500 lbs./ac.	30 lbs./ac. 5/
7. Warm season grasses	First	6-12-12	1500 lbs./ac.	50-100 lbs./ac. 2/6/
	Second Maintenance	6-12-12 10-10-10	800 lbs./ac. 400 lbs./ac.	50-100 lbs./ac. 2/ 30 lbs./ac.
8. Warm season grasses and legumes	First	6-12-12	1500 lbs./ac.	50 lbs./ac. 6/
	Second Maintenance	6-12-12 10-10-10	1000 lbs./ac. 400 lbs./ac.	—

- 1/ Apply in spring following seeding.
- 2/ Apply in split applications when high rates are used.
- 3/ Apply in 3 split applications.
- 4/ Apply when plants are pruned.
- 5/ Apply to grass species only.
- 6/ Apply when plants grow to a height of 2 to 4 inches.

Table 6-5-2. Permanent Cover Crops PLANT, PLANTING RATE, AND PLANTING DATE FOR PERMANENT COVER 1				
Species	Broadcast Rates	Resource Area ²	Planting Dates by Resource Area	Remarks
BAHIA, PENSACOLA <i>Paspalum notatum</i>	Rate Per Acre ³ Per 1000 sq ft	Pure Live Seed (PLS) Per 1000 sq ft	J F M A M J J A S O N D	166,000 seed per pound. Low growing. Good for erosion. Slow to establish. Plant with a companion crop. Will spread no bermuda seedlings and areas. Mix with Sericea lespedeza or weeping lovegrass.
alone or with temporary cover	60 lbs	1.4 lbs	P	—
with other perennials	30 lbs	0.7 lb	C	—
BAHIA, WILMINGTON <i>Paspalum notatum</i>	Rate Per Acre ³ Per 1000 sq ft	Pure Live Seed (PLS) Per 1000 sq ft	J F M A M J J A S O N D	166,000 seed per pound. Low growing. Good for erosion. Slow to establish. Plant with a companion crop. Will spread no bermuda seedlings and areas. Mix with Sericea lespedeza or weeping lovegrass.
alone or with temporary cover	60 lbs	1.4 lb	M-L	—
with other perennials	30 lbs	0.7 lb	P	—
BERMUDA, COMMON <i>Cynodon dactylon</i>	Rate Per Acre ³ Per 1000 sq ft	Pure Live Seed (PLS) Per 1000 sq ft	J F M A M J J A S O N D	166,000 seed per pound. Low growing. Good for erosion. Slow to establish. Plant with a companion crop. Will spread no bermuda seedlings and areas. Mix with Sericea lespedeza or weeping lovegrass.
Hulled seed alone	10 lbs	0.2 lb	P	—
with other perennials	6 lbs	0.7 lb	P	—
BERMUDA, COMMON <i>Cynodon dactylon</i>	Rate Per Acre ³ Per 1000 sq ft	Pure Live Seed (PLS) Per 1000 sq ft	J F M A M J J A S O N D	166,000 seed per pound. Low growing. Good for erosion. Slow to establish. Plant with a companion crop. Will spread no bermuda seedlings and areas. Mix with Sericea lespedeza or weeping lovegrass.
Unhulled seed alone	10 lbs	0.2 lb	P	—
with temporary cover	6 lbs	0.1 lb	C	—
with other perennials	6 lbs	0.1 lb	C	—

1/ Apply in spring following seeding.

2/ Apply in split applications when high rates are used.

3/ Apply in 3 split applications.

4/ Apply when plants are pruned.

5/ Apply to grass species only.

6/ Apply when plants grow to a height of 2 to 4 inches.

Table 6-5-3. Permanent Cover Crops PLANT, PLANTING RATE, AND PLANTING DATE FOR PERMANENT COVER 1				
Species	Broadcast Rates	Resource Area ²	Planting Dates by Resource Area	Remarks
LESPEDEZA <i>Amorpha virginica</i>	Rate Per Acre ³ Per 1000 sq ft	Pure Live Seed (PLS) Per 1000 sq ft	J F M A M J J A S O N D	166,000 seed per pound. Low growing. Good for erosion. Slow to establish. Plant with a companion crop. Will spread no bermuda seedlings and areas. Mix with Sericea lespedeza or weeping lovegrass.
Unscarified	75 lbs	1.7 lb	P	—
Scarified	60 lbs	1.4 lb	P	—
LESPEDEZA, SHRUB <i>Lespedeza bicolor</i>	Rate Per Acre ³ Per 1000 sq ft	Pure Live Seed (PLS) Per 1000 sq ft	J F M A M J J A S O N D	166,000 seed per pound. Low growing. Good for erosion. Slow to establish. Plant with a companion crop. Will spread no bermuda seedlings and areas. Mix with Sericea lespedeza or weeping lovegrass.
Unscarified	75 lbs	1.7 lb	P	—
Scarified	60 lbs	1.4 lb	P	—
LESPEDEZA, WEEDING <i>Eragrostis curvula</i>	Rate Per Acre ³ Per 1000 sq ft	Pure Live Seed (PLS) Per 1000 sq ft	J F M A M J J A S O N D	166,000 seed per pound. Low growing. Good for erosion. Slow to establish. Plant with a companion crop. Will spread no bermuda seedlings and areas. Mix with Sericea lespedeza or weeping lovegrass.
Unscarified	75 lbs	1.7 lb	P	—
Scarified	60 lbs	1.4 lb	P	—

1/ Apply in spring following seeding.

2/ Apply in split applications when high rates are used.


3/ Apply in 3 split applications.

4/ Apply when plants are pruned.

5/ Apply to grass species only.

6/ Apply when plants grow to a height of 2 to 4 inches.

Table 6-5.3					Table 6-5.4	
Durable Shrubs and Ground Covers for Permanent Cover					Common Name	Scientific Name
Ground covers include a wide range of low-growing plants planted together in considerable numbers to cover large areas of the landscape. Ground covers grow slower than trees and shrubs are likely to compete, especially the first year. Maintenance is needed to insure survival. These ground covers will be not need unless proper maintenance is planned. Maintain much at three-inch thickness until plants provide adequate cover.					Reasenders	Ilex crenata
Full planning is encouraged because the need for constant watering is reduced and plants have time to establish new roots before hot weather.					Andorra Juniper	Juniperus horizontalis
Common Name	Scientific Name	Mature Height	Plant Spacing	Comments	Andorra Juniper <td>Juniperus horizontalis</td>	Juniperus horizontalis
Albota	Abelia grandiflora	3-4 ft.	5 ft.	Also a prostrate form with light, Sun, semi-shade. Semi-evergreen.	Andorra Juniper	Juniperus horizontalis
Carolina Yellow Jessamine	Gelsemium sempervirens	low	3 ft.	Vine. Yellow, trumpet-like flowers. Hardy, one of best vines. Evergreen. Native to Georgia.	Blue Chip Juniper	Juniperus horizontalis
Carpel Blue	Aluea reptans	2-4 in.	3 ft.	Needs good drainage, partial shade. Blue or white flowers.	Blue Rug Juniper	Juniperus horizontalis
Bearberry	Cotoneaster dammeri	2-4 ft.	5 ft.	White flowers, red fruit. Sun. Evergreen.	Parsons Juniper	Juniperus horizontalis
Grand Cover Cotoneaster	Cotoneaster salicifolius 'Reptens'	1-2 ft.	5 ft.	White flowers, red fruit. Sun. Evergreen.	Parsons Juniper	Juniperus horizontalis
Rock Cotoneaster	Cotoneaster horizontalis	1-2 ft.	5 ft.	Semi-evergreen.	Pfitzer Juniper	Juniperus chinensis
Virginia Creeper	Parthenocissalis quinquefolia	low	3 ft.	Red in fall. Vine. Deciduous. Native to Georgia.	Prince of Wales Juniper	Juniperus horizontalis



EROSION, SEDIMENTATION & POLLUTION CONTROL PLAN CHECKLIST

STAND ALONE GUIDANCE CONSTRUCTION PROJECTS GAR100001

SWDC:

Project Name: SOIL EROSION PLANS

Address: LOT 14C, MOSAIC CIRCLE

Local Issuing Authority: POOLIER

Date on Plans: MARCH, 2025

Name & Email of person filling out checklist: MARK BOSWELL / LAHBOS@BELLSOUTH.NET

Plan Included

Page # Y/N

20 YES

TO BE SHOWN ON ES&PC PLAN

1 The applicable Erosion, Sedimentation and Pollution Control Plan Checklist established by the Commission as of January 1 of the year in which the land-disturbing activity was permitted.

2 Level II certification number issued by the Commission, signature and seal of the certified design professional.

3 Limits of disturbance shall be less than 50 acres at any time without prior written authorization from the GAEPD District Office. If GAEPD approves the request to disturb 50 acres or more at any one time, the Plan must include the GAEPD approval letter and completed Appendix 1 of this checklist with at least 4 of the chosen BMPs.

4 The name and phone number of the 24-hour contact responsible for erosion, sedimentation and pollution controls.

5 Provide the name, address, email address, and phone number of Primary Permittee.

6 Note total and disturbed acreages of the project or phase under construction.

7 Provide the GPS location of the construction exit for the site. Give the Latitude and Longitude in decimal degrees.

8 Initial date of the Plan and the dates of any revisions made to the Plan including the entity who requested the revisions.

9 Descriptions of the nature of construction activity and existing site conditions.

10 Provide vicinity map showing site's relation to surrounding areas. Include designation of specific phase, if necessary.

11 Identify the project receiving waters and describe all sensitive adjacent areas including streams, lakes, residential areas, wetlands, marshlands, etc. which may be affected.

12 Design professional's certification statement and signature that the site was visited prior to development of the ES&PC Plan as stated on Part IV page 20 of the permit.

13 Design professional's certification statement and signature that the Permittee's ES&PC Plan provides for an appropriate and comprehensive system of BMPs and sampling to meet permit requirements as stated on Part IV page 20 of the permit.

14 Clearly note the statement that "The design professional who prepared the ES&PC Plan is to inspect and certify the installation of the initial sediment storage requirements and perimeter control BMPs within 7 days after installation."

15 Provide a description of any buffer encroachments and indicate whether a buffer variance is required.

16 Clearly note the statement that "Amendments/revisions to the ES&PC Plan which have a significant effect on BMPs with a hydraulic component must be certified by the design professional."

17 Clearly note the statement that "Waste materials shall not be discharged to waters of the State, except as authorized by a Section 404 permit."

18 Clearly note statement that "The escape of sediment from the site shall be prevented by the installation of erosion and sediment control measures and practices prior to land disturbing activities."

19 Clearly note statement that "Erosion control measures will be maintained at all times. If full implementation of the approved Plan does not provide for effective erosion control, additional erosion and sediment control measures shall be implemented to control or treat the sediment source."

19 YES

NA NO

NA NO

21 YES

21 YES

21 YES

21 YES

19 YES

21 YES

15-17 NO

20 YES

21 Clearly note the statement "Any disturbed area left exposed for a period greater than 14 days shall be stabilized with mulch or temporary seeding."

22 Any construction activity which discharges storm water into a Biot Impaired Stream Segment, or within 1 linear mile upstream of and within the same watershed as any portion of a Biot Impaired Stream Segment, must comply with Part III.C. of the permit. Include the completed Appendix 1 of this checklist with at least 4 of the chosen BMPs that will be used for those areas of the site which discharge to the Impaired Stream Segment.

23 If a TMDL Implementation Plan for sediment has been finalized for the Biot Impaired Stream Segment (identified in Item 22 above) at least six months prior to substantial of NOI, the ES&PC Plan must address any site-specific conditions or requirements included in the TMDL Implementation Plan.

24 BMPs for concrete washdown of tools, concrete mixer chutes, hoppers and the rear of the vehicles. Include statement that washout of the drum at the construction site is prohibited.

25 Provide BMPs for the remediation of all petroleum spills and leaks.

26 Description of the measures that will be installed during the construction process to control pollutants in storm water that will occur after construction operations have been completed.

27 Description of practices to provide cover for building materials and building products on site.

28 Description of the practices that will be used to reduce the pollutants in storm water discharge.

19 YES

19 YES

21 YES

21 YES

19 YES

21 YES

15-17 NO

20 YES

29 Description and chart or timeline of the intended sequence of major activities which disturb soils for the major portions of the site (i.e., initial perimeter and sediment storage BMPs, clearing and grubbing activities, excavation activities, utility activities, grading, infrastructure, temporary and final stabilization).

30 Provide complete requirements of Inspection and record keeping by the Primary Permittee.

31 Provide complete requirements of Sampling Frequency and Reporting of sampling results.

32 Provide complete details for Retention of Records as per Part IV.F. of the permit.

33 Description of analytical methods to be used to collect and analyze the samples from each location.

34 Appendix B rationale for NTU values at all outfall sampling points where applicable.

35 Delineate all sampling locations on all phases of the Plan, and perennial and intermittent streams and other water bodies into which storm water is discharged.

36 A description of appropriate controls and measures that will be implemented at the construction site including: (1) initial sediment storage requirements and perimeter control BMPs, (2) intermediate grading and drainage BMPs, and (3) final BMPs.

19 YES

19 YES

21 YES

21 YES

19 YES

21 YES

15-17 NO

20 YES

ALL YES

37 Graphic scale and North arrow.

ALL YES

38 Existing and proposed contour lines with contour lines drawn at an interval in accordance with the following:

NA NO

39 Use of Alternative BMPs whose performance has been documented to be equivalent to or superior to conventional BMPs as certified by a Design Professional (unless disapproved by GAEPD or the Georgia Soil and Water Conservation Commission). Refer to the Alternative BMP Guidance Document found at www.gaswcc.georgia.gov.

NA NO

40 Use of Alternative BMP for application to the Equivalent BMP List. Refer to Appendix A-2 of the Manual for Erosion & Sediment Control in Georgia 2016 Edition.

NA NO

41 Delineation of the applicable 25-foot or 50-foot undisturbed buffers adjacent to State Waters and any additional buffers as required by the Local Issuing Authority. Clearly note and delineate all areas of impact.

19 YES

42 Delineation of all State Waters and wetlands located on or within 200 feet of the project site.

REPORT YES

43 Delineation and acreage of contributing drainage basins on the project site.

REPORT YES

44 Provide hydrology study and maps of drainage basins for both the pre- and post-developed conditions.

REPORT YES

45 Estimate of the runoff coefficient or peak discharge flow of the site prior to and after construction activities are completed.

REPORT NO

46 Storm-drain pipe and weir velocities with appropriate outlet protection to accommodate discharges without erosion. Identify/Delineate all storm water discharge points.

19 YES

47 Soil series for the project site and their delineation.

15-17 YES

48 The limits of disturbance for each phase of construction.

20 YES

49 Provide a minimum of 67 cubic yards of sediment storage per acre drained using a temporary sediment basin, retrofitted detention pond, and/or excavated inlet sediment traps for each common drainage location.

19 YES

50 Location of Best Management Practices that are consistent with, and no less stringent than, the Manual for Erosion and Sediment Control in Georgia.

15-17 YES

51 Provide detailed drawings for all structural practices.

15-17 YES

52 Provide negative plan, noting all temporary and permanent vegetative practices.

15-20 YES

50 Location of Best Management Practices that are consistent with, and no less stringent than, the Manual for Erosion and Sediment Control in Georgia.

15-20 YES

51 Provide detailed drawings for all structural practices.

15-17 YES

52 Provide negative plan, noting all temporary and permanent vegetative practices.

* If using this checklist for a project that is less than 1 acre and not part of a common development but within 200 ft of a perennial stream the * checklist items would be N/A.

Effective January 1, 2025

WETLAND / BUFFER ENCROACHMENT NOTES:

1. NEW STRUCTURES ON THIS PROJECT DO NOT ENCROACH IN THE 25 OR 50 FOOT STREAM BUFFER.

2. NON-EXEMPT ACTIVITIES SHALL NOT BE CONDUCTED WITHIN THE 25 OR 50 FOOT STREAM BUFFER AS MEASURED FROM THE POINT OF WRESTED VEGETATION WITHOUT FIRST OBTAINING THE NECESSARY VARIANCES AND PERMITS.

DESCRIPTION OF STORM WATER POLLUTION DISCHARGE PREVENTION PRACTICES

I. THE FOLLOWING IS A DESCRIPTION OF THE PRACTICES TO BE USED BUT NOT LIMITED TO:

- A. CONSTRUCTION EXIT
- B. SILT FENCING
- C. TEMPORARY SEDIMENT BASINS
- D. HAY BALE CHECK DAMS
- E. STONE CHECK DAMS
- F. STORM OUTLET PROTECTION
- G. GRASSING
- H. DETENTION POND
- I. SKIMMER
- J. DUST CONTROL
- K. CONCRETE WASHDOWN PIT

SPECIAL CONSTRUCTION NOTE:

IF THE CONTRACTOR KNOWS OR CAN REASONABLY BE EXPECTED TO HAVE KNOWN OF AN ERROR, DISCREPANCY OR CONFLICT IN THE PLANS, SPECIFICATIONS OR CONSTRUCTION STAKING AND FAILS TO REPORT THE PROBLEM PRIOR TO CONSTRUCTION, HE SHALL NOT BE ENTITLED TO COMPENSATION FOR ANY WORK OR EXPENSE INCURRED BY HIM FOR WORK REQUIRED TO BE RE-CONSTRUCTED BECAUSE OF SAID ERROR, DISCREPANCY OR CONFLICT.

LEVEL II
CERTIFICATION
NO. 2104
ISSUED 11-5-05
EXPIRES 11-15-26

MOSAIC GALLERIA
125 HIGH AVENUE
POOLER, GEORGIA 31322
MOSAIC FIVE, LLC
BEAUFORT, SOUTH CAROLINA
GSWCC CHECKLIST

DRAWING NUMBER

C-28

28 OF 28 SHEETS

REVISIONS					

BOSWELL DESIGN SERVICES, INC.

OFFICE: 4700 EAST HIGHWAY 80
Unit N, Suite 1
MAILING: 103 NASSAU DRIVE
SAVANNAH, GEORGIA 31410
912 - 897 - 6932
LAHBOS@Bellsouth.net